

PATENT APPLICATION

IN THE UNITED STATES PATENT AND TRADEMARK OFFICE

Attorney

Docket: 6313-29114

Applicant: JONES, Charles W.

Invention: STEREOGRAPHIC BOOK

International

Serial No: PCT/US97/18028

International

Filing Date: 03 October 1997
(03.10.97)

Earliest Priority

Date: 04 October 1996
(03.10.96)

Certificate Under 37 CFR 37 CFR 1.10

Express Mail Label No.: EM3428692745

Date of Deposit: 04 MAY 1998

I hereby certify that this paper or fee is being deposited
with the United States Postal Service's "Express Mail Post
Office to Address" service under 37 CFR 1.10 on the date
indicated above and is addressed to the Assistant
Commissioner for Patents, Washington, D.C. 20231.

MARY JEAN ESKRIDGE

Typed or Printed Name of Person Mailing Paper or Fee

Mary Jean Eskridge

Signature of Person Mailing Paper or Fee

LETTER ACCOMPANYING AMENDMENT UNDER ARTICLE 34(2)(b)Attn: IPEA/US
Box PCT
Assistant Commissioner for Patents
Washington, D.C. 20231

Sir:

Attached are replacement pages 3, 8 and 18-23 to replace pages 3, 8 and 18-23
of the application as originally filed, and replacement sheets 8/14 and 14/14 to replace sheets
8/14 and 14/14 of the drawings filed with the Response on November 25, 1997.

In the Description

The description as originally filed is amended at page 3, line 24; page 8, line 6;
and page 19, line 5, 10 and 20, to correct typographical errors.

The description as originally filed is amended at page 18, line 25, to include
reference to viewer 7Q.

In the Claims

Original claims 1, 2, 5, 6, 10, 11-14, 16, and 17 are amended.

Original claims 3, 4, 7-9, and 15 remain unchanged.

Claims 18-21 are added.

In the Drawings


Replacement drawing sheets 8/14 and 14/14 are amended to add arrowheads which were inadvertently omitted from Fig. 24 and to correct reference number designations 8R and 7Z in Fig. 39 and 7Q, 8K, and 8L in Fig. 40.

REMARKS

No amendment is believed to go beyond the disclosure in the international application as originally filed.

It is respectfully requested that the International Preliminary Examining Authority start the international preliminary examination on the basis of the international application as amended herewith. It is also requested that the Examiner issue a favorable preliminary Examination Report or, in the alternative, a first Written Opinion.

Respectfully submitted,



Timothy E. Niednagel
Registration No. 33,266

TEN/nw
Indianapolis, Indiana
(317)231-7551

INTERNATIONAL APPLICATION PUBLISHED UNDER THE PATENT COOPERATION TREATY (PCT)

(51) International Patent Classification⁶ :

G02B 27/22

A1

(11) International Publication Number:

WO 98/14819

(43) International Publication Date:

9 April 1998 (09.04.98)

(21) International Application Number: PCT/US97/18028

(22) International Filing Date: 3 October 1997 (03.10.97)

(30) Priority Data:

60/026,761

4 October 1996 (04.10.96)

US

60/044,736

18 April 1997 (18.04.97)

US


(71)(72) Applicant and Inventor: JONES, Charles, W. [US/US];
P.O. Box 161, Knightstown, IN 46148 (US).(74) Agent: NIEDNAGEL, Timothy, E.; Barnes & Thornburg, 11
South Meridian Street, Indianapolis, IN 46204 (US).(81) Designated States: CA, JP, US, European patent (AT, BE, CH,
DE, DK, ES, FI, FR, GB, GR, IE, IT, LU, MC, NL, PT,
SE).

Published

With international search report.

Before the expiration of the time limit for amending the
claims and to be republished in the event of the receipt of
amendments.

(54) Title: STEREOGRAPHIC BOOK



(57) Abstract

A stereographic device includes a content support portion (8) configured to position and support stereographic content (1A, 1B), and a stereoscopic viewer (5) configured to enable interocular adjustment. The stereoscopic viewer includes adjustable left and right viewpoint lens arrangements, and adjustable occluding apertures configured for interpupillary alignment relative to the stereographic content. A viewer pivotal chassis (3) is configured to couple the stereoscopic viewer to the content support portion (8). The viewer pivotal chassis includes a plurality of pivotal axes (3) parallel to an axis common to the left and right lenses of the stereoscopic viewer to enable the viewer to be movable in a linear direction perpendicular to the stereoscopic lense axis.

FOR THE PURPOSES OF INFORMATION ONLY

Codes used to identify States party to the PCT on the front pages of pamphlets publishing international applications under the PCT.

AL	Albania	ES	Spain	LS	Lesotho	SI	Slovenia
AM	Armenia	FI	Finland	LT	Lithuania	SK	Slovakia
AT	Austria	FR	France	LU	Luxembourg	SN	Senegal
AU	Australia	GA	Gabon	LV	Latvia	SZ	Swaziland
AZ	Azerbaijan	GB	United Kingdom	MC	Monaco	TD	Chad
BA	Bosnia and Herzegovina	GE	Georgia	MD	Republic of Moldova	TG	Togo
BB	Barbados	GH	Ghana	MG	Madagascar	TJ	Tajikistan
BE	Belgium	GN	Guinea	MK	The former Yugoslav Republic of Macedonia	TM	Turkmenistan
BF	Burkina Faso	GR	Greece	ML	Mali	TR	Turkey
BG	Bulgaria	HU	Hungary	MN	Mongolia	TT	Trinidad and Tobago
BJ	Benin	IE	Ireland	MR	Mauritania	UA	Ukraine
BR	Brazil	IL	Israel	MW	Malawi	UG	Uganda
BY	Belarus	IS	Iceland	MX	Mexico	US	United States of America
CA	Canada	IT	Italy	NE	Niger	UZ	Uzbekistan
CF	Central African Republic	JP	Japan	NL	Netherlands	VN	Viet Nam
CG	Congo	KE	Kenya	NO	Norway	YU	Yugoslavia
CH	Switzerland	KG	Kyrgyzstan	NZ	New Zealand	ZW	Zimbabwe
CI	Côte d'Ivoire	KP	Democratic People's Republic of Korea	PL	Poland		
CM	Cameroon	KR	Republic of Korea	PT	Portugal		
CN	China	KZ	Kazakhstan	RO	Romania		
CU	Cuba	LC	Saint Lucia	RU	Russian Federation		
CZ	Czech Republic	LI	Liechtenstein	SD	Sudan		
DE	Germany	LK	Sri Lanka	SE	Sweden		
DK	Denmark	LR	Liberia	SG	Singapore		
EE	Estonia						

STEREOGRAPHIC BOOKBackground and Summary of the Invention

5 The present invention relates to an articulated apparatus which enables stereographic and textual content to be conveyed and presented to the user in a manner similar and related to a book; a brochure; and a format for advertisement and presentation in concert with pre-existing publishing and packaging formats.

10 The present invention may also be configured with transparent sleeves which operate in a manner similar to a plurality of pivotally-mounted pages, so it may convey stereographic photoprints mounted back-to-back in a manner similar to a photo album.

The present invention can convey high resolution stereographic digital hard copies sent and received via an electronic network, to be printed at the site of reception, and then mounted into the device.

15 The present invention can be configured to convey stereographic charts and maps to enhance the user's comprehension of geographical and topological features.

More particularly, the present invention as contemplated herein is directed to providing a stereographic device which is very affordable to produce with pre-existing materials and manufacturing techniques extant in the publishing industry, including
20 materials such as cardboard, bristol board, fabric, linen, etc. (with the exception of the lens elements, which are plastic or glass) and with such manufacturing methods as die-cutting, folding, laminating, etc. and other pre-established methods of fastening and page binding, including staple, wire, etc. The present invention can be secured together and also releasably secured into a storage configuration with various printable adhesives, tapes
25 and also tab and slot fastening techniques common to the traditional publishing industry and well known to those skilled in the art. However, the present invention should not be limited to these suggested aspects of material preference and said rendering techniques, as other means may be utilized to render the device in its various configurations.

30 Stereographic/stereoscopic devices are numerous and various in type and well-known in the art. Generally, a stereoscope is an optical instrument configured to view stereographic imagery. The primary objective of the stereoscopic/stereographic art is to provide the user with a visual medium that approximates the experience of natural

human visual perception of three-dimensional space. Depth perception is a phenomenon that naturally occurs as the right and left eyes each perceive simultaneously the spacial world in parallax, from two slightly different, horizontally displaced perspective viewpoints, which the brain fuses together and interprets, providing three-dimensional perception. A stereographic image typically consists of two separate images produced in a flat, planar, two-dimensional medium. The images of corresponding left and right perspective views are appropriately positioned next to each other so that their perspective viewpoints are horizontally displaced from each other by a distance that corresponds to the average inter-pupillary distance of the left and right eyes. The two images, commonly referred to as a stereograph or a stereo-pair, when viewed with an optical viewer possessing two lenses with the appropriate optical and focal properties, enable each eye to see the corresponding image intended for it, thereby creating in the brain a perceived three-dimensional effect.

The present invention is designed to take advantage of the high-tech synthesizing power of computer imaging as well as high resolution digital printing to provide an affordable, accessible stereographic book that is capable of communicating complex three-dimensional visual concepts which are accompanied and augmented with textual information. Because of its ability to store and convey both stereographic imagery and readable text, the present invention can be utilized extensively for educational and entertainment purposes. In particular, the present invention is useful for visual novels and children's books, including reading primers, and also as an affordable, take-home visualization tool and study aid in the fields of chemistry, molecular biology, medicine, architecture, artistic sculpture, and other areas which benefit from seeing and understanding complex three-dimensional imagery.

Description of the Invention

Stereoscopic Viewer

The stereoscopic viewer, including its various adaptations as disclosed herein, has the primary objective of conveying stereographic content to the user. Further, the objective is to simulate natural human vision and to inclusively provide an immersive,

full-field-of-view stereographic viewing experience to a wide audience, especially those who do not have access to expensive electronic systems.

One of the key capabilities necessary to achieve this objective is interocular adjustment. The present viewer substantially improves this capability over the previously disclosed and claimed embodiments of this inventor's work as originally filed in U.S. Patent No. 5,499,136, wherein interocular adjustment was achieved by configuring the lenses to be adjustable to the user's individual interpupillary distance, with occluding apertures in a fixed and integral position in the viewer body. This capability is effective to a certain extent, however, it is determined that remarkably improved perception of the immersive image field can be attained by configuring the apertures which frame the left and right images to also be adjustable, to therewith enable right-stereographic content to be occluded from the left eye viewpoint and left-stereographic content to be occluded from the right-eye viewpoint, respectively.

Further, adjustable occluding apertures greatly improve the user's ability to fine-tune and thus see an immersive visual-field that simulates natural vision, with a central stereo-field bordered by left and right peripheral monocular fields. The apertures' close proximity to the user's eyes renders the perception of the shielding edges of the apertures as a soft blur. This soft blur of occlusion is actually very important, because it blends said stereo and mono fields seamlessly together, to create an immersive visual field.

It is annotated that the viewer of the present invention may be configured with any type of lense optics common to the stereoscopic art, including but not limited to the double convex, double convex wedge, plano convex, plano convex wedge, agstigmatic double convex, agstigmatic plano convex, and any other optical lense form or arrangement of lense forms which facilitate optical utilization of the stereoscopic viewer.

Chassis Pivotal Geometries

The pivotal geometries of the chassis portions designated herein as the viewer pivotal chassis (VPC) achieves a substantial improvement over the previous viewer pivotal array (VPA) geometries disclosed in U.S. Patent No. 5,499,136, specifically in embodiments 13C, 14D, and 15E of said patent, which are concerned with enabling the device to achieve a first and second viewing position so that two pivotally-

exposed stereographic pages may be viewed sequentially. The VPC geometries presently contemplated achieve not only first and second viewing positions, but are also capable of a linear scanning movement between the first and second viewing positions while retaining focus of the two pivotally-exposed pages. This enables stereographic content on said pages to be arranged in new ways, for example, a double-page spread of a single stereographic image can be viewed. This viewing procedure provides a sensation similar to one surveying a space with binoculars, in the aspect that one can roam and traverse up and down the double page spread and the 3D space of the image. This capability cannot be achieved by the VPA geometries of said previous embodiments. The present VPC geometries are substantially different as to function, and also achieve said functional articulation with a greater economy of pivotal movement. Other distinctions between said previously disclosed VPA geometries and the present VPC geometries are:

Specifically, said previous VPA geometries as disclosed in U.S. Patent No. 5,499,136 in embodiments 13C, 14D, and 15E in Figs. 29, 30, and 34, 35 respectively, indicates a mid-point pivotal axis which is required to rotate approximately 180° from the first viewing position to the second viewing position. This is easily discernable in said Figs., as the mid-point pivot apex is in an inverse position in the first viewing position and then shifts approximately 180° to an obverse position in the second viewing position. This reciprocal angular shift is repeated as the pages are pivoted and viewed and can be considered appropriate if placed in the context of the preferred materials of plastic and metal, as contemplated in U.S. Patent No. 5,499,136, where a repeated and high degree of pivotal flex is easily withstood.

However, the embodiments presently contemplated herein are directed towards material preferences and manufacturing techniques that are traditional to the publishing industry, i.e. cardboard and fabric. Said previous VPA geometries as disclosed in U.S. Patent No. 5,499,136 may rapidly fatigue and damage cardboard and fabric pivotal means, so the present VPC geometries disclosed herein are contemplated as pivotal solutions to these material concerns. However, it should be understood that these stated aspects of material preference do not exclude the application and rendering of these herein disclosed pivotal configurations with other materials and techniques, i.e. the present invention can also be rendered in plastic or metal or other materials.

According to another aspect of distinction, the present VPC geometries disclosed herein do not require a mid-point pivotal axis to rotate 180° as in said previous embodiments. The present VPC geometries do not possess a mid-point pivot and the pivotal axes have been changed so that no pivot apex of the VPC shifts from an inverse to an obverse position. All pivot apexes of the present VPC geometries retain an obverse angular relationship. Further, the present VPC geometries require less pivotal rotation and do not require any pivotal axis to rotate 180°. Thus, pivotal wear is substantially reduced, and the aforesaid linear scanning function is an additional benefit to the present invention. The drawings disclosed herein will provide a corresponding description of these objectives and said geometries.

Brief Description of the Drawings

A complete understanding of the present invention and other advantages and features thereof may be gained from a consideration of the following description of the preferred embodiments taken in conjunction with the accompanying drawings in which:

Fig. 1 is a perspective view of stereographic book 16 illustrating the viewer, chassis, page mount/content support portion with a stereographic content packet 1.

Fig. 2 is a side perspective view of book 16 in a first-viewing position with said content packet in place.

Fig. 3 is a side perspective view of book 16 in a second-viewing position revealing the pivotal articulation of the chassis relative to Fig. 2.

Fig. 4 is an end elevation view of book 16 in a folded storage configuration.

Fig. 5 is an exploded view, in perspective, illustrating the various adjustable elements of the stereoscopic viewer 5.

Fig. 6 is an end perspective view of book 16 illustrating a preferred position to place the device on a horizontal surface so the elements of the viewer 5 can be easily adjusted and aligned with the stereographic content alignment targets 10L and 10R.

Fig. 7 is a sectional illustration from the point of view of the user, including the fingers of the user, indicating the adjustment and alignment features of the

stereoscopic viewer 5 relative to a schematic diagram of the perceptual visual fields of the stereographic content.

Fig. 8 is a schematic diagram of the perceptual visual fields of stereographic content 1V, before visual field fusion.

5 Fig. 9 is a schematic diagram of the perceptual visual fields of stereographic content 1V, after visual field fusion, which corresponds to Fig. 8.

Fig. 10 is a perspective view of book 16 illustrating the method to grasp the device with hands 21L and 21R.

10 Fig. 11 is a perspective sectional view of said content packet 1 and page mount/content support portion 8 with a user's fingers portrayed in a page-turning procedure.

Fig. 12 is a perspective sectional view that corresponds with Fig. 11 to portray a page-turning procedure.

15 Figs. 13-17 are corresponding perspective views of book 16 illustrating in sequential steps how content packet 1C can be utilized.

Fig. 18 is a side perspective view of book variation 17 in a first-viewing position.

Fig. 19 is a side perspective view of book 17 in a second-viewing position, revealing the pivotal articulation of the chassis relative to Fig. 18.

20 Fig. 20 is an end-elevational view of book 17 in a folded storage configuration.

25 Fig. 21 is a perspective view of book variation 18 in a first-viewing position, revealing the modifications of the chassis pivotal geometry, the extended content support portion which is adapted to support the pages in a generally common plane, and a schematic diagram of multiple picture areas that may be utilized for creating stereographic comics.

Fig. 22 is a perspective view of book 18 in a second-viewing position, revealing the pivotal articulation of the chassis relative to Fig. 21.

30 Fig. 23 is an end-elevational view of book 18 in a folded storage configuration.

Fig. 24 is a perspective view of a stereographic magazine insert, brochure 19, which illustrates how the pivotal chassis of the present invention can be adapted to

scan or traverse a series of stereographic images arranged on a content support portion consisting of a planar sheet or surface.

Fig. 25 is an end-elevational view illustrating the thin profile of brochure 19 and viewer 5C in a folded configuration.

5 Fig. 26 is a perspective view of a stereographic packaging adaptation, 20, illustrating how the content support portion, pivotal chassis and viewer 5C may be adapted to packaging, such as toy and cereal boxes, or other such packaging as whimsy permits.

10 Fig. 27 is an exploded front-perspective view of viewer 5D, which is configured with adjustable occluding apertures 6E and lenses 4E.

Fig. 28 is a perspective view of elements 4M and 6D, which are variations of the adjustable lens and occluding aperture elements relative to viewer 5D in Fig. 27.

Fig. 29 is a perspective view of element 4Y, which integrates the lens 4N and occluding aperture 6L into one unit and is relative to viewer 5D in Fig. 27.

15 Fig. 30 is a front view of viewer 5M, which utilizes pivotal means to achieve interocular adjustment.

Fig. 31 is an exploded view, in perspective, of elements 6M, 4S and 5N relative to viewer 5M in Fig. 30.

20 Fig. 32 is a front view of element 4Z, which integrates the lens 4V and occluding aperture 6R into one unit, relative to viewer 5M in Fig. 30.

Fig. 33 is a frontal exploded view, in perspective, of interocular adjustment mechanism 5Q, which enables the lenses and occluding apertures to be adjusted in a synchronized manner by the user.

25 Fig. 34 is a frontal perspective view of mechanism 5Q, showing the components assembled and indicating the directional motion of the components when the mechanism is being adjusted to accommodate a user with narrow-set eyes.

Fig. 35 is a frontal view which closely corresponds to Fig. 34, and indicates the directional motion of the components when the mechanism is being adjusted to accommodate a user with wide-set eyes.

30 Fig. 36 is a frontal exploded view, in perspective, of mechanism 5U, a means to achieve synchronous interocular adjustment with a simple arrangement of gears.

Fig. 37 is a front elevation view of mechanism 5U which indicates the directional motion of the components during said adjustment.

Fig. 38 is a front elevational view of viewer 7Q, which utilizes a fulcrum and pivotal arm to achieve synchronous lense and aperture adjustment movement in a manner similar to mechanism 5Q of Figs. 33-35, except that the adjustment means of 7Q are disposed between the lenses and apertures.

Fig. 39 is a perspective view of book 70, which portrays viewer 7Q being utilized to create a hybrid stereographic book with a reinforced fabric pivotal chassis and content support portion.

Fig. 40 is an end elevational view of the device of Fig. 39 in a storage configuration.

Detailed Description of the Drawings

Referring to the drawings, Fig. 1 illustrates stereographic book 16 which includes stereoscopic viewer 5. The parallel pivotal axes 3 of the viewer pivotal chassis (VPC) are revealed and pivotally coupled to page mount/content support portion 8 which is configured with sleeve 8A which slidably receives cover 7 of stereographic content packet 1, as indicated by arrows, one of which is designated as 22.

Fig. 2 indicates book 16 in a first viewing position, whereby viewer 5 is aligned and focused as indicated by arrow 21 by the user pivoting VPC3 and page surface 1A which is pivoted on axis 1P, which is established and determined by the engagement of cover 7 of content packet 1 therewith sleeve 8A of page mount/content support portion 8.

Fig. 3 indicates book 16 in a second viewing position whereby the pivotal articulation of VPC3 has shifted to align viewer 5 with page surface 1B. Arrow 23 indicates that the pivotal rotation of the indicated plurality of pages of content packet 1 can be selectively rotated in either direction. It is understood that the stereographic content on page surfaces 1A and 1B is oriented in an upright position relative to viewer 5.

Fig. 4 provides an end elevational view of book 16 which indicates the position of the viewer 5, content packet 1, page mount/content support portion 8 and VPC3 when conformed into a protective storage configuration.

Fig. 5 is an exploded view of viewer 5 which reveals the folded and beveled construction of viewer body 5V which includes apertures 5A. Also revealed are

lens elements 4 which may be pre-existing molded plastic or glass. The exploded view reveals how right lens 4 securely engages socketed aperture 4A of lens carriage 4D, configured with bevels 4B to slidably engage occluding aperture plate 6, configured with occluding aperture 6A and corresponding bevels 6B, which also slidably engage bevels 5B of viewer body 5V as indicated by arrow 24. Slidable adjustment of lens carriages 4D and aperture plates 6 is achieved by the user grasping control tabs 4C and 6C, respectively. It should be understood that lens 4 can be rendered integrally and merged with lens carriage 4D, without changing its ability to be independently adjustable relative to aperture 6. Lens 4 may be configured to be integral and one piece with aperture 6A, however, if these two features are merged, independent adjustment between lens 4 and aperture 6A is lost.

Fig. 6 illustrates book 16 in a horizontal position, preferably resting on a surface, to thereby enable the user to use both hands to adjust and align the lenses and apertures of viewer 5 relative to the schematic targets 10L and 10R on page surface 1A, so that the user's individual optical requirements can be met.

Fig. 7 is an illustration from the point of view of the user, including a schematic diagram 1Q indicating the perceptual visual fields which compose the stereographic content to be perceived by the user with viewer 5; said fields 2L and 2R as indicated by the diagonal lines will compose the central stereofield when fused in the brain of the user. The fields 2DL and 2DR, indicated with horizontal lines, will compose the left and right peripheral monocular fields, respectively, after fusion by the user. Centerline 13, where the left 2L field and the right 2R field abut, will be occluded to non-visibility; this is achieved, as represented by dotted line 14, by the user moving index fingers 9L and 9R to slide, as indicated by arrows 11, aperture control tabs 6C and therewith occluding apertures 6A so that said apertures enable each eye of the user to only see the appropriate visual fields intended for it. The procedure for adjusting the lenses of viewer 5 is similar, whereby the user moves thumbs 15L and 15R to slide, as indicated by arrows 12, lens carriage control tabs 4C and therewith lenses 4, until the targets indicated in schematic stereofields 2L and 2R successfully fuse into one target. Thus, inter-pupillary alignment with the stereographic content is achieved. This process is further revealed in Figs. 8 and 9.

Fig. 8 is a schematic diagram which indicates the perceptual visual fields which compose the stereographic content 1V before the event of fusion by the user. Left

and right stereofields 2L and 2R are schematically represented by the diagonal lines as indicated, respectively. Alignment targets 10L and 10R are represented with inner circles of a different diameter as indicated. Peripheral monofields 2DL and 2DR are represented by horizontal lines as indicated. Centerline 13 is indicated between stereofields 2L and 2R.

It is annotated that the primary objective of abutting stereofields 2L and 2R is to achieve perception of the largest stereofield possible. If a wide central border were interposed between 2L and 2R, said border would occupy space that can be utilized by the stereographic content and decrease and narrow the perceived stereofield, thus the objective of attaining an immersive visual field would be diminished. However, it should be understood that non-immersive stereographic content can also be conveyed with the present invention, for example, the perceived visual field can convey a series of 3D images, in a manner similar to comics.

Fig. 9 is a corresponding schematic diagram relative to Figs. 7 and 8, which indicates stereographic content IV after the event of fusion by the user. Central stereofield 3D is indicated by diagonal dotted lines as bracketed. Central stereofield 3D is composed of stereofields 2L and 2R (refer to Fig. 8) which have fused, as indicated by arrows 50. Alignment targets 10L and 10R have now fused, and the inner circles of different diameters are indicated (refer to Fig. 8). Peripheral monofields 2DL and 2DR are indicated. Centerline 13 is indicated by two dotted lines, and it should be understood that centerline 13 would not be visible if it is successfully occluded. If not properly occluded, centerline 13 would occupy the areas indicated, i.e., centerline 13 would appear as two hard-edged bands containing overlapped stereographic imagery which would not fuse properly, one on each side of stereofield 3D between monofields 2DL and 2DR.

When properly occluded, centerline 13 is blocked out by apertures 6A (See Fig. 7) so that monofields 2DL and 2DR merge with stereofield 3D. This perceptual merging is greatly improved by the close proximity of apertures 6A to the user's eyes, which renders the occluding edge of each aperture 6A as a soft blur, which aids in seamlessly blending the stereofield 3D and monofields 2DL and 2DR together.

When the apertures 6A are adjustable to the user's exact visual requirements said field merging effect is virtually indistinguishable from natural visual perception.

Fig. 10 illustrates in perspective the preferred method of holding the present invention after viewer 5 has been adjusted by the user. Book 16 and viewer pivotal chassis 3 is shown in a second-viewing position, aligned with page 1B after surveying page 1A. Viewer 5 is held by hand 21L and finger 9L and thumb 15L are indicated. Hand 21R is holding page mount/content support portion 8 and securing, with finger 9R and thumb 15R, the plurality of pages of content packet 1 in a viewing position. Note how finger 9R can keep the page surfaces 1A and 1B in position, i.e., spread apart from each other and in a fairly general focal plane which can be intuitively manipulated by the user. It is understood that hand 21L could hold said content packet 1 and hand 21R could hold viewer 5.

Fig. 11 relates to Fig. 10 and directly corresponds to Fig. 12 and is a perspective sectional view of content packet 1 and page mount/content support portion 8 being held by hand 21R with thumb 15R and finger 9R turning page 1S whereby arrow 25 indicates the motion of thumb 15R creating a curl in page 1S. Index finger 9R is portrayed as inserted as indicated by arrow 26 under said curl.

Fig. 12 continues correspondence with the Fig. 11 page turning procedure, whereby thumb 15R has pulled back as indicated by arrow 27 thereby releasing page 1S, and index finger 9R has flipped page 1S in the direction indicated by arrow 28, thereby pivoting page 1S on pivotal axis 1P into a first-viewing position. Page 2S is revealed in a second-viewing position.

Figs. 13 through 17 illustrate therewith corresponding perspective views of book 16 a sequential procedure for utilizing content packet 1C, which is a plurality of pages wire-bound with a conventional, well-known binding, 2Y. Page 1D and 1E are shown with schematic symbols to diagram the orientation of the stereographic content, whereby the arrows of 1D are pointing upward towards page pivotal axis 2P and the striped arrows of 1E are also oriented towards said axis 2P. Fig. 13 indicates viewer 5 in alignment to view 1D, which is oriented correctly. It is understood that a plurality of pages can be pivotally-exposed and the stereographic content therewith would be oriented said same as indicated by 1D, and that viewer 5 would enable the user to view said pages in sequence.

Fig. 14 shows the cover 7 of content packet 1C being slidably released from sleeve 8A of page mount/content support portion 8 as indicated by two arrows, one of which is designated as 29.

Fig. 15 portrays content packet 1C being reoriented as indicated by arrows 30 and 31, so that page 1E is approaching upright orientation relative to book 16.

Fig. 16 illustrates 1C approaching, as indicated by arrow 32, slidable engagement with sleeve 8A of page mount/content support portion 8 of book 16.

Fig. 17 portrays content packet 1C in place so that the stereographic content as diagrammed with 1E can be pivoted on page axis 2P as indicated by arrow 33, and viewed in an upright orientation with viewer 5. It is understood that the content diagrammed on the page surface 1D is arrayed on the opposite side of the page surface diagrammed as 1E.

Fig. 18 is a side perspective view of book variation 17 in a first-viewing position, illustrating an adaptation of the pages 1F, pivotable page support surface/cover 7B and page mount/content support portion 8B to a traditional wire-bound format, 3R. It is understood that pages 1F would not be removable with this adaptation. Viewer 5 is unchanged from previous Figs. The VPC3A pivotal geometry is virtually identical to previous VPC3 geometry herein.

Fig. 19 illustrates book variation 17 in a second-viewing position. Wire-binder 3R establishes page pivotal axis 3P.

Fig. 20 is an end elevational view of book 17, indicating the position of the various components in a storage configuration. Wire-binder 3R is evident and cover 7B is indicated in proximity with viewer 5.

Fig. 21 is a perspective view of book variation 18 in a first-viewing position, whereby viewer 5 is aligned to enable the user to view page surface 1J of content packet 1I which is a plurality of pages bound with conventional stapling means 7D to mounting strip 8C which can be affixed to cover/content support portion 7C with a variety of means, such as adhesives or tab and slot techniques common in the art, to determine page pivotal axis 4P. The viewer pivotal chassis axes 3B are clearly indicated, as is the obverse pivotal geometry of said VPC, whereby all angular apexes of said VPC3B are pointed outward in an externally-oriented conformation. Viewer 5 is unchanged relative to previous Figs.

Page 1J and 1K are supported in a generally common plane by extended and rigid cover/content support portion 7C, and are shown with a diagram of multiple stereographic panels as a suggestion to how said pages may convey stereographic comics. As previously stated herein (refer to description of Fig. 8) such an arrangement of stereographic content would be non-immersive, but it could still be fun to view.

Fig. 22 corresponds to Fig. 21, indicating book 18 in a second-viewing position. Viewer 5 can retain focus and vertically scan and traverse page surfaces 1L and 1M respectively, as indicated by arrow 34. Pages 1L and 1M are illustrated to indicate that a single vertical image may be arranged therewith said page surfaces, so that viewer 5 may be utilized by the user to rove over the double-page spread. This would be very appropriate for viewing stereographic topological surface maps, or for surveying the topology of a pretty girl in a bathing suit.

Fig. 23 is an end elevational view of book 18 in a folded storage configuration. The extension of cover 7C is visible, as is the placement of the pivotal axes of VPC3B. Viewer 5 is said same.

Fig. 24 is a perspective view of a stereographic publication insert, brochure 19, which illustrates how the means of the present invention can be adapted to such an objective.

Whereby publication 9M (pictured here as a magazine, however, the brochure 19 may be inserted into other publishing formats) is attached thereto planar sheet/content support portion 7E with any number of well-known and conventional means thereto 9S, and may also be removed from publication 9M by common means, an example of which is illustrated here as perforated line 7F. Also indicated are suggested corresponding configurations for releasably securing viewer 5C and VPC3C into a flat configuration parallel therewith planar sheet 7E, whereby when so conformed, tab 8D engages slot 8E, tab 8F engages slot 8G, tab 9A engages slot 9B and tab 9C engages 9D in a fastening manner commonly known in the art. It is annotated that these suggested and indicated fastening means, methods, and typical locations of engagement are simply a few of a myriad of ways the present invention can be releasably fastened to achieve the objective of said flat configuration.

Viewer 5C is functionally the same as viewer 5, except that it is thinner in profile, and is pivotably coupled to VPC3E which is very similar in function to VPC3B

pivotal geometry of book 18 shown in Figs. 21-23, whereby viewer 5C can easily scan and traverse a series of stereographic images as indicated therewith 1N, while maintaining focus, with proper manipulation by the user in the direction indicated by arrow 35.

It should be understood that an additional purpose for this particular Fig. 24 configuration, other than functioning as a brochure/insert, can be anticipated. For example, planar sheet/content support portion 7E may also be configured to function as a planar mounting surface similar to a common clipboard, to which flat sheets of stereographic content can be aligned and releasably fastened for viewing.

It should be understood that planar sheet/content support portion 7E may also be easily configured with a plurality of pivotable pages in a manner similar to that illustrated in Figs. 21-23.

Fig. 25 is an end elevational view of brochure 19 illustrating the thin profile of brochure 19 and viewer 5C in a folded configuration with sheet 7E.

Fig. 26 is a perspective view of a stereographic packaging adaptation, 20, illustrating how the means of the present invention may be adapted to such a purpose, to enliven packaging with 3D viewing.

Whereby stereographic content 1R is either integral or affixed to package 7G, and VPC3E is, in the example shown here, attached thereto package 7G by glued flap 8H. A suggested example is indicated of releasably fastening viewer 5C and VPC3E into a flat configuration, parallel to the plane defined by 1R, wherewith tab 9E engages slot 9F, and tab 9G engages slot 9H. It is understood that VPC3E and viewer 5C function in the same manner as previously disclosed Figs. 21-25.

Fig. 27 is an exploded, sectional, front-perspective view of stereoscopic viewer 5D, which is configured with adjustable occluding aperture units 6D and adjustable lens units 4I, and is adaptable to all the embodiments contemplated herein and additionally useful and applicable to the present invention should it be rendered in plastic or metal, as viewer 5D would be more durable. Also, viewer 5D would be applicable to linen/hardcover renditions of the embodiments 16, 17, and 18, whereby the entire arrangement of the viewer 5D components can snap thereon to cardboard chassis plate 5L therewith holes 5H which are of a diameter to securely engage the snap studs 5J of bridgepiece 5I, said studs 5J also engage viewer body holes 5G, two of which are indicated. Lenses 4E engage into snap rim 4F as indicated by arrow 37. The aperture

units 6D and lens units 4I nest together in a parallel plane in viewer eyepiece wells 5K so that lenses 4E, apertures 6E are adjustably aligned with viewer apertures 5E. The beveled surfaces 4G and 6F of the lens units 4I and aperture units 6D, respectively, slidably fit in the channel indicated by 5F. Adjustment handles 4H of lens units 4I slidably contact
5 surface 6G. When snapped into place, lens units 4I and aperture units 6D independently slide in the direction indicated by arrows 38 and 39, respectively.

It should be understood that said apertures and lenses in all the embodiments disclosed may be configured with other means to achieve the stated objectives of the present invention, and that, for example, the apertures could be arranged
10 on the opposite side of the lenses so that they are closer to the user's eyes than said lenses.

Fig. 28 is an exploded view, in perspective, of one of the two lens units 4M and aperture units 6D which correspond to viewer 5D in Fig. 27, whereby the configuration of lens 4J and unit 4M are integral and merged into one piece.

Said units fit and function in the viewer 5D in the same manner as units 4I
15 and 6D described in Fig. 27.

Fig. 29 is a perspective view of one of two lens/aperture elements 4Y, which integrates lens 4N with occluding aperture 6L to form one adjustable piece which fits into viewer 5D of Fig. 27 to fulfill the functions of a lens unit 4I and aperture unit 6D. However, it is understood that this configuration does not enable independent adjustment
20 between said lenses and apertures.

Fig. 30 is a front elevational, sectional view of stereoscopic viewer 5M, which is adaptable to the present invention, and utilizes pivotal means to achieve adjustment of the lenses 4R and occluding apertures 6N, whereby the entire arrangement of viewer 5M components engage mounting plate 5T therewith mounting holes, one of
25 which is indicated as 5Z, which are of a diameter to secure snap-studs 5N, which also engage and secure viewer body 5Y, therewith mounting holes, one of which is indicated as 5X. Snap-studs 5N also pivotally couple lens units 4S and aperture units 6M together so they may pivot about axes determined by mounting holes 5Z, 5X, and stud 5N in the directions indicated by arrows 43 and 46. Pivotal adjustment of lenses 4R and apertures
30 6N is achieved by the user utilizing the index fingers to nudge switches 4T and 6P, respectively.

Fig. 31 is an exploded view, in perspective, which relates to viewer 5M of Fig. 30, whereby one snap-stud 5N is indicated, as are pivotal collars 6Q and 4X, of left aperture unit 6M and lens unit 4S, respectively. Pivotal axis 5P is indicated as common to said components.

5 Fig. 32 is a front elevational view of a left integral lens/aperture unit, 4Z, which can be utilized therewith viewer 5M of Fig. 30, whereby the lens 4V is merged and molded in one piece with occluding aperture 6R and pivotal collar 5S.

 Fig. 33 is a frontal exploded view of interocular adjustment mechanism 5Q, which enables a synchronous adjustment of the eyepieces. It is annotated that the
10 mechanism 5Q does not enable independent adjustment between the lenses and occluding apertures; however, 5Q does allow interocular adjustment to be quickly achieved by the novice stereographic book user. The mechanism depicted is configured to be mounted within a cardboard viewer body as previously shown (see Fig. 5, No. 5V), which is omitted here for purposes of clarity. The components depicted are fabricated of thin,
15 vacuum formed and die-cut plastic, except for the lenses 4Q, which may be pre-existing injection molded plastic or glass. The components of 5Q are basically thin plastic membranes, rendered in a manner familiar to those skilled in the art. It should be understood that the components of 5Q could also be fashioned of injected-molded plastic, cardboard with rivet pivots, or stamped and die-cut aluminum. Mechanism 5Q as shown
20 is extremely cost-effective to produce and reasonably durable.

 Fig. 33 indicates how lenses 4L snap into lens sockets 4K which are die-cut to form integral occluding apertures 6K which are positioned on lens carriage elements 4W and 4Y, respectively. It is understood that lenses 4L could be merged and formed integrally with said carriage elements via injection-molding. Carriage element 4W
25 includes thumb-switch 4U which indicates a typical location the user would grasp the mechanism 5Q, between the left thumb and forefinger. Carriage element 4W also includes stabilizing channel 6X the concave underside of which slidably fits over the convex upperside of stabilizing channel 6Y of carriage unit 4Y in a manner similar to nesting cups; thus, channel 6Y then also slidably fits over stabilizing alignment pin 6Z,
30 formed on base plate 5W. This same nesting/fitting technique is also evident in the assembly of pivotal sockets 6S and 6U of carriage units 4W and 4Y to pivotal arm pins 6T and 6V respectively, located on pivotal arm 6I, which in turn, fits similarly via fulcrum

pivotal socket 6H to fulcrum pin 6W, formed on base plate 5W, which also includes die-cut eyepiece apertures 5R. It is annotated that base plate 5W is aligned and secured with any number of typical fastening techniques within a viewer body such as 5V of Fig. 5. However, it should be understood that there are many other means to establish a fulcrum or stabilize the simple pivotal geometry of mechanism 5Q which may not require a base plate such as 5W. Base plate 5W is depicted for reasons of graphic clarity.

Fig. 34 depicts mechanism 5Q assembled and illustrates the directional motion of the components to adjust the eyepieces to a narrow eye setting, whereby thumb switch 4V is slid in the direction indicated by arrow 51, sliding carriage unit 4W and thus pivotal socket 6S in the same direction as arrow 52; pivotal socket 6S, which engages pivotal arm pin 6T, causing pivotal arm 6I to pivot via fulcrum pivotal socket 6H and fulcrum pin 6W in a clockwise movement as indicated by arrow 53; thus moving pivotal arm pin 6V, which engages pivotal socket 6U, causing carriage 4Y to slide in the direction indicated by arrow 54. Nested stabilizing channels 6X and 6Y and stabilizing alignment pin 6Z are indicated and it is annotated that they may serve to maintain carriages 4W and 4Y in slidable alignment and also serve as a means of stopping or limiting the distance of carriage travel to an appropriate interocular adjustment range. It should be understood that this function can be achieved by other alternative means, and that the present invention is not limited to this specific depicted configuration.

Fig. 35 is a perspective view of mechanism 5Q from an identical point of view as Fig. 34, so the two Figs. can be quickly compared. Fig. 35 indicates the directional motion of the components of 5Q when it is adjusted for a wide eye setting. Arrows 55 through 58 basically indicate the same movement of the said same components as in Fig. 34 in the opposite direction. The angle of pivotal arm 6I can be seen to be stopped in a different position relative to its position in Fig. 34. This angular difference can be seen by comparing line 59 of Fig. 35 to line 60 of Fig. 34.

Fig. 36 illustrates yet another simple means to achieve synchronized interocular adjustment, whereby the lenses and occluding apertures are moved away or towards each other in concert by utilizing a pinion gear meshed with opposing linear gears. Exploded perspective Fig. 36 illustrates mechanism 5U, whereby clear, injection-molded eyepiece components 3U and 3K, which each are configured with lens 3L, integral occluding aperture 3N, and thumb switch 3S slidably fit into eyepiece well 3W of

viewer body 3Y, which is configured with eyepiece apertures 3X and gear pivot pin 3H, which receives gear sleeve 3V of pinion gear 3G so that pinion gear 3G rotates freely in either direction, and meshes with opposing linear gears 3Z and 3T of eyepieces 3J and 3K, respectively. It is annotated that these designated components can be pivotally and
5 slidably secured into place by any number of typical methods, for example, a capping shell which would nest over viewer body 3Y and thus maintain said movable components in the eyepiece well 3W. Also, as illustrated in Fig. 27, viewer body 3Y can be secured to a viewer pivotal chassis (or formed integrally with said same) with any number of techniques. Fig. 36 is mainly concerned with revealing mechanism 5U.

10 Fig. 37 is a front elevational view of mechanism 5U which corresponds with Fig. 36, and portrays the assembled components and the directional motion of said components as they are adjusted to accommodate a user with wide-set eyes. It is understood that the basic mechanical directions and motions portrayed in Fig. 37 can also occur in the opposite directions as indicated so as to achieve interocular adjustment for a
15 narrow eye-setting.

A wide interocular adjustment is achieved when the user grasps eyepiece thumb switch 3S and slides it outward as indicated by arrows 61 and 65. It is understood that the user may grasp either the left or right thumb switch. For this sequential example, the user slides the left switch 3S in the direction indicated by arrow 61, which causes
20 linear gear 3Z to also slide, as indicated by arrow 62, which in turn pivots pinion gear 3G in a clockwise motion around gear pivot pin 3H as indicated by arrow 63, thus driving the meshed teeth of opposing linear gear 3T in the direction indicated by arrow 64, thereby sliding eyepiece 3K in a synchronized manner away from eyepiece 3J, as indicated by arrow 65.

25 Fig. 38 illustrates how fulcrum 7P and pivotal arm 7R may be positioned between the lenses 7L and occluding apertures 7I, the pivotal couplings 7N and 7M engaging corresponding means configured with lense carriages 7H and 7U, respectively. These pivotal couplings can be made in a number of techniques common to the mechanical art, nested plastic pins and sockets, rivets, etc. The lense carriages 7H and 7U
30 may be integral with the lenses 7L and apertures 7I and may include adjustment switches 7S. The lense carriages are slidably positioned and limited in their movement by positioning apertures 7J, which slidably engage pins 7K; which are integral with base plate

7T, which also integrally includes living hinge 3I and insert plate 7V, shown in section. It is annotated that hinge 3I and plate 7V are shown as one of many possible ways to provide a corresponding means of engaging the viewer to the other components of the present invention, so that the pivotal function of the device as claimed may be achieved; however, the present invention should not be limited to these illustrated means. The advantage of locating the fulcrum and pivotal arm between the lenses is fairly straight forward; this enables adjustment switches 7S to be located on each side of the viewer so it may be adjusted with either hand while viewing.

Fig. 39 depicts book 7O and how 7Q may be configured with insert plate 7V to engage, as indicated by the arrows 80, sleeve 8N of viewer pivotal chassis 8M, which is constructed of fabric with rigid plates sewn within so that the device can maintain its pivotal and support functions. It is understood that once insert plate 7V is slid into position, the viewer pivotal chassis geometry is rendered functional as claimed, and the axes designated as 3I pivot in the same manner as in previous figures.

The pivotal page support 8N, which includes two pivotal axes 3M, also functions as a cover flap and can be releasably secured to 8M with sewn velcro patches or other means common in the art, whereby patch 8I engages patch 8J and 8K engages 8L, respectively.

The content packet 7Y is shown in place, positioned, as shown in Fig. 1, by the packet sheet 7Y being slid into sleeve 8S on the content support portion 8Q, thus determining page pivotal axis 7W.

Stereographic content 7X is thereby positioned to be viewable as depicted in previous figures.

Fig. 40 is an end view of the present invention in a folded storage mode which reveals the components of the present invention.

Whereas the present invention is susceptible of various modifications and alternative constructions, the embodiments suggested in the drawings will herein be described in sufficient detail. It should be understood, however, it is not the intention to limit the invention to the particular forms disclosed, but to indicate the general spacial alignments and inherent geometries and thus define the functional and objective parameters of the present invention.

Claims:

1. A stereographic device comprising
a content support portion configured with means to position and support
5 stereographic content;
stereographic content positioned and supported with the content support
portion;
a stereoscopic viewer configured with means to enable interocular
adjustment, including adjustable left and right viewpoint lense arrangements, and
10 adjustable occluding apertures configured to enable right stereographic content to be
occluded from the left eye viewpoint and left stereographic content to be occluded from
the right eye viewpoint, respectively;
the adjustable lense arrangements and occluding apertures configured to
enable interpupillary alignment relative to the stereographic content positioned and
15 supported with the content support portion when conformed into a viewing configuration;
a viewer pivotal chassis configured with corresponding means to couple
the means of the stereoscopic viewer to the content support portion so that the viewer
pivotal chassis is interposed between the stereoscopic viewer and the content support
portion;
20 the viewer pivotal chassis including a plurality of pivotal axes parallel to an
axis common to the left and right lenses of the stereoscopic viewer;
the viewer pivotal chassis configured with the parallel axes to enable the
viewer to be movable in a linear direction perpendicular to the stereoscopic lense axis;
within a focal plane and at a focal length determined by the user, relative and parallel to
25 the stereographic content provided with the content support portion when conformed into
a viewing configuration.
2. A modification of the device of claim 1, whereby the content
support portion is configured with means to position and support an axis to enable a
plurality of pages to be pivotable, the axis being parallel to an axis common to the left and
30 right lenses of the viewer; the pages provided with stereographic content that is viewable
with the viewer when conformed into a viewing configuration.

3. A variation of the device of claim 2, whereby the content support portion is configured to position and support the page axis and the plurality of pages provided with stereographic content, to thereby enable two pivotally exposed pages, which are adjacent to and opposite each other and disposed one on each side of the page axis, to be viewable with the viewer when conformed into a viewing configuration.

4. A variation of the device of claim 3, whereby the content support portion includes a pivotable page support surface with at least one pivotable axis parallel and generally adjacent to the page pivotal axis; the surface and axes configured to provide support and facilitate viewing of the pivotally exposed pages with the viewer when conformed into a viewing configuration.

5. A modification of the device of claim 2, whereby the plurality of pivotable pages, each having first and second opposite surfaces, are provided therewith stereographic content, the upright direction of the content oriented towards the pivotal axis of the pages, the axis provided with releasably attachable corresponding means to engage the content support portion, to enable the upright content of the first surfaces to be attachable to the content support portion and thereby viewable with the viewer, released, reoriented and reattached to enable the upright content of the second surfaces to be viewable with the viewer in a viewing conformation.

6. An adaptation of the device of claim 2, whereby the plurality of pages are configured to convey photographic media, including stereographic prints, one of the means of page configuration including transparent sleeves to enable photographic media to be positioned, supported and thereby viewable with the viewer when conformed into a viewing configuration.

7. A modification of the device of claim 1, whereby the content support portion is configured to position, support and releasably engage at least one sheet provided with stereographic content.

8. A variation of the device of claim 1, whereby the content support portion consists of a planar surface provided with stereographic content.

9. A variation of the device of claim 1, whereby the content support portion is configured with a sleeve to slidably receive and thereby position and support a releasably attachable content packet consisting of a plurality of pages configured to be pivotable about an axis, the sleeve enabling the page axis to be positioned parallel to an

axis common to the left and right lenses of the viewer, so that the stereographic content provided with the pages is viewable with the viewer when conformed into a viewing configuration.

10. A variation of the stereographic viewer of the device of claim 1,
5 whereby the means of the adjustable left and right lenses are configured to enable independent adjustment relative to each other and also relative to the means of the independently adjustable left and right occluding apertures.

11. A variation of the stereoscopic viewer of the device of claim 1,
10 whereby the means of the independently adjustable left and right lenses are functionally integrated with the left and right occluding apertures, respectively; so that adjustment of the lenses determines a corresponding adjustment of the occluding apertures.

12. A variation of the stereoscopic viewer of the device of claim 1,
15 whereby the adjustable left and right lenses are functionally integrated with the left and right occluding apertures, respectively; so that adjustment of the lenses determines a corresponding adjustment of the occluding apertures; the function of adjustment enabled with means that synchronize equidistant movement of the left and right lenses and respective occluding apertures towards or away from each other.

13. A variation of the stereoscopic viewer of claim 12, whereby the
20 synchronized equidistant movement of the left and right lenses and respective occluding apertures towards or away from each other is enabled with the means of a pivotal arm positioned by a fulcrum, one end of the arm being pivotally coupled to the means of the left lense and occluding aperture, the other end of the pivotal arm being pivotally coupled to the means of the right lense and occluding aperture.





14. A variation of the stereoscopic viewer of claim 12, whereby the
25 synchronized equidistant movement of the left and right lenses and respective occluding apertures toward or away from each other is enabled by rotational movement of a pinion gear meshed with two opposing linear gears, each of which slide on an axis parallel to an axis common to the left and right lenses, one of the linear gears being functionally coupled to the means of the left lense and occluding aperture; the other linear gear being
30 functionally coupled to the means of the right lense and occluding aperture.

15. A modification of the device of claim 1, whereby the content
support portion, the stereoscopic viewer and the viewer pivotal chassis are pivotally

conformable into a storage configuration that interposes the lenses of the stereoscopic viewer in a shielded position between the viewer pivotal chassis and the content support section.

16. A variation of the storage configuration of claim 15, whereby the
5 content support portion, the stereoscopic viewer, and the viewer pivotal chassis are maintained in the storage configuration with corresponding, releasable fastening means.

17. An improvement of the device of claim 1, whereby the
stereographic content provided with the content support portion is configured to convey
to the user, with the means of the stereoscopic viewer when conformed into a viewing
10 configuration, a visual field of view, including left and right peripheral fields of two-dimensional perception interposed by a central binocular stereo field of three-dimensional perception.






FIG. 6




FIG. 7




FIG. 8




FIG. 9




FIG. 10




FIG. 11





FIG. 12










FIG. 18




FIG. 19





FIG. 20








FIG. 24





FIG. 25




FIG. 27





FIG. 28




FIG. 29

FIG. 30




FIG. 31




FIG. 32




FIG. 33




FIG. 34




FIG. 35




FIG. 36








FIG. 37





INTERNATIONAL SEARCH REPORT

International application No.
PCT/US97/18028**A. CLASSIFICATION OF SUBJECT MATTER**

IPC(6) : Please See Extra Sheet.

US CL : 359/474, 476, 477, 467

According to International Patent Classification (IPC) or to both national classification and IPC

B. FIELDS SEARCHED

Minimum documentation searched (classification system followed by classification symbols)

U.S. : 359/474, 476, 477, 467

Documentation searched other than minimum documentation to the extent that such documents are included in the fields searched
359/466

Electronic data base consulted during the international search (name of data base and, where practicable, search terms used)

C. DOCUMENTS CONSIDERED TO BE RELEVANT

Category*	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
A	US 5,499,136 A (JONES) 12 March 1996 (12.03.96), see entire document.	1-17
A	US 5,309,280 A (JONES) 03 MAY 1994 (03.05.94), see entire document.	1-17
A	US 4,172,633 A (HASHIMOTO ET AL) 30 OCTOBER 1979 (30.10.79), see entire document, especially column 2, lines 23-30.	1-17
A	US 472,196 A (McGrew) 05 April 1892 (05.04.92), see entire document.	1-17
A	US 2,616,333 A (TINKER) 04 NOVEMBER 1952 (04.11.52), see entire document.	1-17
A	US 174,893 A (BIERSTADT) 21 MARCH 1876 (21.11.76), see entire document.	1-17

☐ Further documents are listed in the continuation of Box C. ☐ See patent family annex.

* Special categories of cited documents:	"T" later document published after the international filing date or priority date and not in conflict with the application but cited to understand the principle or theory underlying the invention
"A" document defining the general state of the art which is not considered to be of particular relevance	"X" document of particular relevance; the claimed invention cannot be considered novel or cannot be considered to involve an inventive step when the document is taken alone
"E" earlier document published on or after the international filing date	"Y" document of particular relevance; the claimed invention cannot be considered to involve an inventive step when the document is combined with one or more other such documents, such combination being obvious to a person skilled in the art
"L" document which may throw doubts on priority claim(s) or which is cited to establish the publication date of another citation or other special reason (as specified)	"&" document member of the same patent family
"O" document referring to an oral disclosure, use, exhibition or other means	
"P" document published prior to the international filing date but later than the priority date claimed	

Date of the actual completion of the international search

18 MARCH 1998

Date of mailing of the international search report

18 MAR 1998

Name and mailing address of the ISA/US
Commissioner of Patents and Trademarks
Box PCT
Washington, D.C. 20231

Facsimile No. (703) 305-3230

Authorized officer

JON W. HENRY

Telephone No. (703) 305-6106

INTERNATIONAL SEARCH REPORT

International application No.
PCT/US97/18028

A. CLASSIFICATION OF SUBJECT MATTER:
IPC (6):

GO2B/27/22

PATENT COOPERATION TREATY

PCT

NOTIFICATION OF ELECTION

(PCT Rule 61.2)

From the INTERNATIONAL BUREAU

To:

United States Patent and Trademark
Office
(Box PCT)
Crystal Plaza 2
Washington, DC 20231
ETATS-UNIS D'AMERIQUE

in its capacity as elected Office

Date of mailing (day/month/year) 12 June 1998 (12.06.98)	
International application No. PCT/US97/18028	Applicant's or agent's file reference 6313-29114
International filing date (day/month/year) 03 October 1997 (03.10.97)	Priority date (day/month/year) 04 October 1996 (04.10.96)
Applicant JONES, Charles, W.	

1. The designated Office is hereby notified of its election made:

☒ in the demand filed with the International Preliminary Examining Authority on:

04 May 1998 (04.05.98)

☐ in a notice effecting later election filed with the International Bureau on:

2. The election
- ☒
- was

☐ was not

made before the expiration of 19 months from the priority date or, where Rule 32 applies, within the time limit under Rule 32.2(b).

The International Bureau of WIPO
34, chemin des Colombettes
1211 Geneva 20, Switzerland

Facsimile No.: (41-22) 740.14.35

Authorized officer

C. Carrié

Telephone No.: (41-22) 338.83.38

From the INTERNATIONAL SEARCHING AUTHORITY

MAR 23 1998

PCT
BARNES & THORNBURG

NOTIFICATION OF TRANSMITTAL OF
THE INTERNATIONAL SEARCH REPORT
OR THE DECLARATION

(PCT Rule 44.1)

To: TIMOTHY E. NIEDNAGEL BARNES & THORNBURG 11 SOUTH MERIDIAN STREET INDIANAPOLIS, INDIANA 46204		Date of Mailing (day/month/year) 18 MAR 1998
Applicant's or agent's file reference 6313-29114	FOR FURTHER ACTION See paragraphs 1 and 4 below	
International application No. PCT/US97/18028	International filing date (day/month/year) 03 OCTOBER 1997	
Applicant CHARLES W. JONES		

1. ☒ The applicant is hereby notified that the international search report has been established and is transmitted herewith.

Filing of amendments and statement under Article 19:

The applicant is entitled, if he so wishes, to amend the claims of the international application (see Rule 46):

When? The time limit for filing such amendments is normally 2 months from the date of transmittal of the international search report; however, for more details, see the notes on the accompanying sheet.

Where? Directly to the International Bureau of WIPO
 34, chemin des Colombettes
 1211 Geneva 20, Switzerland
 Facsimile No.: (41-22) 740.14.35

For more detailed instructions, see the notes on the accompanying sheet.

2. ☐ The applicant is hereby notified that no international search report will be established and that the declaration under Article 17(2)(a) to that effect is transmitted herewith.

3. ☐ With regard to the protest against payment of (an) additional fee(s) under Rule 40.2, the applicant is notified that:

☐ the protest together with the decision thereon has been transmitted to the International Bureau together with the applicant's request to forward the texts of both the protest and the decision thereon to the designated Offices.

☐ no decision has been made yet on the protest; the applicant will be notified as soon as a decision is made.

4. **Further action(s):** The applicant is reminded of the following:

Shortly after 18 months from the priority date, the international application will be published by the International Bureau. If the applicant wishes to avoid or postpone publication, a notice of withdrawal of the international application, or of the priority claim, must reach the International Bureau as provided in rules 90 bis 1 and 90 bis 3, respectively, before the completion of the technical preparations for international publication.

Within 19 months from the priority date, a demand for international preliminary examination must be filed if the applicant wishes to postpone the entry into the national phase until 30 months from the priority date (in some Offices even later).

Within 20 months from the priority date, the applicant must perform the prescribed acts for entry into the national phase before all designated Offices which have not been elected in the demand or in a later election within 19 months from the priority date or could not be elected because they are not bound by Chapter II.

Name and mailing address of the ISA/US Commissioner of Patents and Trademarks Box PCT Washington, D.C. 20231 Facsimile No. (703) 305-3230	Authorized officer JON W. HENRY Telephone No. (703) 305-6106
---	--

PCT

INTERNATIONAL SEARCH REPORT

(PCT Article 18 and Rules 43 and 44)

Applicant's or agent's file reference 6313-29114	FOR FURTHER ACTION see Notification of Transmittal of International Search Report (Form PCT/ISA/220) as well as, where applicable, item 5 below.
International application No. PCT/US97/18028	International filing date (day/month/year) 03 OCTOBER 1997
	(Earliest) Priority Date (day/month/year) 04 OCTOBER 1996
Applicant CHARLES W. JONES	

This international search report has been prepared by this International Searching Authority and is transmitted to the applicant according to Article 18. A copy is being transmitted to the International Bureau.

This international search report consists of a total of 3 sheets.

☒ It is also accompanied by a copy of each prior art document cited in this report.

1. ☐ Certain claims were found unsearchable (See Box I).
2. ☐ Unity of invention is lacking (See Box II).
3. ☐ The international application contains disclosure of a nucleotide and/or amino acid sequence listing and the international search was carried out on the basis of the sequence listing
 - ☐ filed with the international application.
 - ☐ furnished by the applicant separately from the international application,
 - ☐ but not accompanied by a statement to the effect that it did not include matter going beyond the disclosure in the international application as filed.
 - ☐ transcribed by this Authority.
4. With regard to the title,
 - ☒ the text is approved as submitted by the applicant.
 - ☐ the text has been established by this Authority to read as follows:
5. With regard to the abstract,
 - ☒ the text is approved as submitted by the applicant.
 - ☐ the text has been established, according to Rule 38.2(b), by this Authority as it appears in Box III. The applicant may, within one month from the date of mailing of this international search report, submit comments to this Authority.
6. The figure of the drawings to be published with the abstract is:
 - Figure No. 10
 - ☒ as suggested by the applicant.
 - ☐ because the applicant failed to suggest a figure.
 - ☐ because this figure better characterizes the invention.
 - ☐ None of the figures.

A. CLASSIFICATION OF SUBJECT MATTER:
IPC (6):

GO2B/27/22

INTERNATIONAL SEARCH REPORT

International application No.
PCT/US97/18028**A. CLASSIFICATION OF SUBJECT MATTER**

IPC(6) : Please See Extra Sheet.

US CL : 359/474, 476, 477, 467

According to International Patent Classification (IPC) or to both national classification and IPC

B. FIELDS SEARCHED

Minimum documentation searched (classification system followed by classification symbols)

U.S. : 359/474, 476, 477, 467

Documentation searched other than minimum documentation to the extent that such documents are included in the fields searched
359/466

Electronic data base consulted during the international search (name of data base and, where practicable, search terms used)

C. DOCUMENTS CONSIDERED TO BE RELEVANT

Category*	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
A	US 5,499,136 A (JONES) 12 March 1996 (12.03.96), see entire document.	1-17
A	US 5,309,280 A (JONES) 03 MAY 1994 (03.05.94), see entire document.	1-17
A	US 4,172,633 A (HASHIMOTO ET AL) 30 OCTOBER 1979 (30.10.79) , see entire document, especially column 2, lines 23-30.	1-17
A	US 472,196 A (McGrew) 05 April 1892 (05.04.92), see entire document.	1-17
A	US 2,616,333 A (TINKER) 04 NOVEMBER 1952 (04.11.52), see entire document.	1-17
A	US 174,893 A (BIERSTADT) 21 MARCH 1876 (21.11.76), see entire document.	1-17

☐ Further documents are listed in the continuation of Box C. ☐ See patent family annex.

* Special categories of cited documents:	"T" later document published after the international filing date or priority date and not in conflict with the application but cited to understand the principle or theory underlying the invention
"A" document defining the general state of the art which is not considered to be of particular relevance	"X" document of particular relevance; the claimed invention cannot be considered novel or cannot be considered to involve an inventive step when the document is taken alone
"E" earlier document published on or after the international filing date	"Y" document of particular relevance; the claimed invention cannot be considered to involve an inventive step when the document is combined with one or more other such documents, such combination being obvious to a person skilled in the art
"L" document which may throw doubts on priority claim(s) or which is cited to establish the publication date of another citation or other special reason (as specified)	"&" document member of the same patent family
"O" document referring to an oral disclosure, use, exhibition or other means	
"P" document published prior to the international filing date but later than the priority date claimed	

Date of the actual completion of the international search

18 MARCH 1998

Date of mailing of the international search report

18 MAR 1998

Name and mailing address of the ISA/US
Commissioner of Patents and Trademarks
Box PCT
Washington, D.C. 20231

Facsimile No. (703) 305-3230

Authorized officer

JON W. HENRY

Telephone No. (703) 305-6186

RECEIVED

PATENT COOPERATION TREATY

WO 98/14819
PCT/US97/18028

APR 26 1998

Keel

BARNES & THORNBURG PCT

From the INTERNATIONAL BUREAU

**NOTICE INFORMING THE APPLICANT OF THE
COMMUNICATION OF THE INTERNATIONAL
APPLICATION TO THE DESIGNATED OFFICES**

(PCT Rule 47.1(c), first sentence)

To:

NIEDNAGEL, Timothy, E.
Barnes & Thornburg
11 South Meridian Street
Indianapolis, IN 46204
ETATS-UNIS D'AMERIQUE

Date of mailing (day/month/year)

09 April 1998 (09.04.98)

Applicant's or agent's file reference

6313-29114

IMPORTANT NOTICE

International application No.

PCT/US97/18028

International filing date (day/month/year)

03 October 1997 (03.10.97)

Priority date (day/month/year)

04 October 1996 (04.10.96)

Applicant

JONES, Charles, W.

1. Notice is hereby given that the International Bureau has communicated, as provided in Article 20, the international application to the following designated Offices on the date indicated above as the date of mailing of this Notice:
CA,EP,JP,US

In accordance with Rule 47.1(c), third sentence, those Offices will accept the present Notice as conclusive evidence that the communication of the international application has duly taken place on the date of mailing indicated above and no copy of the international application is required to be furnished by the applicant to the designated Office(s).

2. The following designated Offices have waived the requirement for such a communication at this time:
None

The communication will be made to those Offices only upon their request. Furthermore, those Offices do not require the applicant to furnish a copy of the international application (Rule 49.1(a-bis)).

3. Enclosed with this Notice is a copy of the international application as published by the International Bureau on
09 April 1998 (09.04.98) under No. WO 98/14819

REMINDER REGARDING CHAPTER II (Article 31(2)(a) and Rule 54.2)

If the applicant wishes to postpone entry into the national phase until 30 months (or later in some Offices) from the priority date, a **demand for international preliminary examination** must be filed with the competent International Preliminary Examining Authority before the expiration of 19 months from the priority date.

It is the applicant's sole responsibility to monitor the 19-month time limit.

Note that only an applicant who is a national or resident of a PCT Contracting State which is bound by Chapter II has the right to file a demand for international preliminary examination.

REMINDER REGARDING ENTRY INTO THE NATIONAL PHASE (Article 22 or 39(1))

If the applicant wishes to proceed with the international application in the **national phase**, he must, within 20 months or 30 months, or later in some Offices, perform the acts referred to therein before each designated or elected Office.

For further important information on the time limits and acts to be performed for entering the national phase, see the Annex to Form PCT/IB/301 (Notification of Receipt of Record Copy) and Volume II of the PCT Applicant's Guide.

The International Bureau of WIPO
34, chemin des Colombettes
1211 Geneva 20, Switzerland

Facsimile No. (41-22) 740.14.35

Authorized officer

J. Zahra

Telephone No. (41-22) 338.83.38

The demand must be filed directly with the competent International Preliminary Examining Authority or, if none, with the one chosen by the applicant. The full name or two-letter code of that Authority may be indicated by the applicant on the line below:

IPEA/ US

PCT

CHAPTER II

DEMAND

under Article 31 of the Patent Cooperation Treaty:
The undersigned requests that the international application specified below be the subject of international preliminary examination according to the Patent Cooperation Treaty.

For International Preliminary Examining Authority use only

Identification of IPEA		Date of receipt of DEMAND	
Box No. I IDENTIFICATION OF THE INTERNATIONAL APPLICATION		Applicant's or agent's file reference 6313-29114	
International application No. PCT/US97/18028	International filing date (day/month/year) (03.10.97) 03 October 1997	(Earliest) Priority date (day/month/year) (04.10.96) 04 October 1996	
Title of invention STEREOGRAPHIC BOOK			
Box No. II APPLICANT(S)			
Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country.) JONES, Charles W. P.O. Box 161 Knightstown, Indiana 46148 US		Telephone No.: None	
		Facsimile No.: None	
		Teleprinter No.:	
State (i.e. country) of nationality: US		State (i.e. country) of residence: US	
Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country.)			
State (i.e. country) of nationality:		State (i.e. country) of residence:	
Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country.)			
State (i.e. country) of nationality:		State (i.e. country) of residence:	
<input type="checkbox"/> Further applicants are indicated on a continuation sheet.			

Box No. III AGENT OR COMMON REPRESENTATIVE: OR ADDRESS FOR CORRESPONDENCEThe following person is ☒ agent ☐ common representativeand ☒ has been appointed earlier and represents the applicant(s) also for international preliminary examination.☐ is hereby appointed and any earlier appointment of (an) agent(s)/common representative is hereby revoked.☐ is hereby appointed, specifically for the procedure before the International Preliminary Examining Authority, in addition to the agent(s)/common representative appointed earlier.Name and address: *(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country.)*

NIEDNAGEL, Timothy E.
BARNES & THORNBURG
 11 South Meridian Street
 Indianapolis, Indiana 46204
 US

Telephone No.:

(317) 236-1313

Facsimile No.:

(317) 231-7433

Teleprinter No.:

☐ Mark this check-box where no agent or common representative is/has been appointed and the space above is used instead to indicate a special address to which correspondence should be sent.**Box No. IV STATEMENT CONCERNING AMENDMENTS**

The applicant wishes the International Preliminary Examining Authority*

(i) ☒ to start the international preliminary examination on the basis of the international application as originally filed.(ii) ☒ to take into account the amendments under Article 34 of☒ the description (amendments attached).☒ the claims (amendments attached).☒ the drawings (amendments attached).(iii) ☐ to take into account any amendments of the claims under Article 19 filed with the International Bureau (a copy is attached).(iv) ☐ to disregard any amendments of the claims made under Article 19 and to consider them as reversed.(v) ☐ to postpone the start of the international preliminary examination until the expiration of 20 months from the priority date unless that Authority receives a copy of any amendments made under Article 19 or a notice from the applicant that he does not wish to make such amendments (Rule 69.1(d)). *(This check-box may be marked only where the time limit under Article 19 has not yet expired.)*

* Where no check-box is marked, international preliminary examination will start on the basis of the international application as originally filed or, where a copy of amendments to the claims under Article 19 and/or amendments of the international application under Article 34 are received by the International Preliminary Examining Authority before it has begun to draw up a written opinion or the international preliminary examination report, as so amended.

Box No. V ELECTION OF STATES☒ The applicant hereby elects all eligible States (that is, all States which have been designated and which are bound by Chapter II of the PCT) except

(If the applicant does not wish to elect certain eligible States, the name(s) or country code(s) of those States must be indicated above.)

Annex to PCT DEMAND under Article 31 of the Patent
Cooperation Treaty
Box No. III AGENT OR COMMON REPRESENTATIVE (Continued)

NIEDNAGEL, Timothy E.; COFFEY, William R.; HYLAND, Jerry E.; CONARD, Richard D.; LAMMERT, Steven R.; REZEK, Richard A.; PALAN, Perry; NEWMAN, Mark M.; GILLENWATER, Bobby B.; GZYBOWSKI, Michael S.; HUNT, Paul B.; BREEN, John P.; WERLING, Jill L.; HARRISON, Nancy J.; CARTER, R. Trevor, NULL, Robert D.; all located at:

BARNES & THORNBURG
11 South Meridian Street
Indianapolis, Indiana 46204
US

Box No. VI CHECK LIST

The demand is accompanied by the following documents for the purposes of international preliminary examination:

- | | | | |
|--|-----|--------|--|
| 1. amendments under Article 34 | | | |
| description | : 4 | sheets | |
| claims | : 4 | sheets | |
| drawings | : 2 | sheets | |
| 2. letter accompanying amendments under Article 34 | : 2 | sheets | |
| 3. copy of amendments under Article 19 | : | sheets | |
| 4. copy of statement under Article 19 | : | sheets | |
| 5. other (specify): | : | sheets | |

For International Preliminary
Examining Authority use only

received

not received


<input type="checkbox"/>	<input type="checkbox"/>
<input type="checkbox"/>	<input type="checkbox"/>
<input type="checkbox"/>	<input type="checkbox"/>
<input type="checkbox"/>	<input type="checkbox"/>
<input type="checkbox"/>	<input type="checkbox"/>
<input type="checkbox"/>	<input type="checkbox"/>
<input type="checkbox"/>	<input type="checkbox"/>

The demand is also accompanied by the item(s) marked below:

- | | |
|--|--|
| 1. <input type="checkbox"/> separate signed power of attorney | 4. <input checked="" type="checkbox"/> fee calculation sheet |
| 2. <input type="checkbox"/> copy of general power of attorney | 5. <input type="checkbox"/> other (specify): |
| 3. <input type="checkbox"/> statement explaining lack of signature | |

Box No. VII SIGNATURE OF APPLICANT, AGENT OR COMMON REPRESENTATIVE

Next to each signature, indicate the name of the person signing and the capacity in which the person signs (if such capacity is not obvious from reading the demand).



Timothy E. Niednagel, Agent for Applicant

For International Preliminary Examining Authority use only

1. Date of actual receipt of DEMAND:

2. Adjusted date of receipt of demand due to CORRECTIONS under Rule 60.1(b):

3. ☐ The date of receipt of the demand is AFTER the expiration of 19 months from the priority date and item 4 or 5, below, does not apply.

☐ The applicant has been informed accordingly.

4. ☐ The date of receipt of the demand is WITHIN the period of 19 months from the priority date as extended by virtue of Rule 80.5.

5. ☐ Although the date of receipt of the demand is after the expiration of 19 months from the priority date, the delay in arrival is EXCUSED pursuant to Rule 82.

For International Bureau use only

Demand received from IPEA on:

full-field-of-view stereographic viewing experience to a wide audience, especially those who do not have access to expensive electronic systems.

One of the key capabilities necessary to achieve this objective is interocular adjustment. The present viewer substantially improves this capability over the previously disclosed and claimed embodiments of this inventor's work as originally filed in U.S. Patent No. 5,499,136, wherein interocular adjustment was achieved by configuring the lenses to be adjustable to the user's individual interpupillary distance, with occluding apertures in a fixed and integral position in the viewer body. This capability is effective to a certain extent, however, it is determined that remarkably improved perception of the immersive image field can be attained by configuring the apertures which frame the left and right images to also be adjustable, to therewith enable right-stereographic content to be occluded from the left eye viewpoint and left-stereographic content to be occluded from the right-eye viewpoint, respectively.

Further, adjustable occluding apertures greatly improve the user's ability to fine-tune and thus see an immersive visual-field that simulates natural vision, with a central stereo-field bordered by left and right peripheral monocular fields. The apertures' close proximity to the user's eyes renders the perception of the shielding edges of the apertures as a soft blur. This soft blur of occlusion is actually very important, because it blends said stereo and mono fields seamlessly together, to create an immersive visual field.

It is annotated that the viewer of the present invention may be configured with any type of lense optics common to the stereoscopic art, including but not limited to the double convex, double convex wedge, plano convex, plano convex wedge, anastigmatic and any other optical lense form or arrangement of lense forms which facilitate optical utilization of the stereoscopic viewer.

Chassis Pivotal Geometries

The pivotal geometries of the chassis portions designated herein as the viewer pivotal chassis (VPC) achieves a substantial improvement over the previous viewer pivotal array (VPA) geometries disclosed in U.S. Patent No. 5,499,136, specifically in embodiments 13C, 14D, and 15E of said patent, which are concerned with enabling the device to achieve a first and second viewing position so that two pivotally-

Fig. 37 is a front elevation view of mechanism 5U which indicates the directional motion of the components during said adjustment.

Fig. 38 is a front elevational view of viewer 7Q, which utilizes a fulcrum and pivotal arm to achieve synchronous lense and aperture adjustment movement in a manner similar to mechanism 5Q of Figs. 33-35, except that the adjustment means of 7Q are interposed between the lenses and apertures.

Fig. 39 is a perspective view of book 70, which portrays viewer 7Q being utilized to create a hybrid stereographic book with a reinforced fabric pivotal chassis and content support portion.

Fig. 40 is an end elevational view of the device of Fig. 39 in a storage configuration.

Detailed Description of the Drawings

Referring to the drawings, Fig. 1 illustrates stereographic book 16 which includes stereoscopic viewer 5. The parallel pivotal axes 3 of the viewer pivotal chassis (VPC) are revealed and pivotally coupled to page mount/content support portion 8 which is configured with sleeve 8A which slidably receives cover 7 of stereographic content packet 1, as indicated by arrows, one of which is designated as 22.

Fig. 2 indicates book 16 in a first viewing position, whereby viewer 5 is aligned and focused as indicated by arrow 21 by the user pivoting VPC3 and page surface 1A which is pivoted on axis 1P, which is established and determined by the engagement of cover 7 of content packet 1 therewith sleeve 8A of page mount/content support portion 8.

Fig. 3 indicates book 16 in a second viewing position whereby the pivotal articulation of VPC3 has shifted to align viewer 5 with page surface 1B. Arrow 23 indicates that the pivotal rotation of the indicated plurality of pages of content packet 1 can be selectively rotated in either direction. It is understood that the stereographic content on page surfaces 1A and 1B is oriented in an upright position relative to viewer 5.

Fig. 4 provides an end elevational view of book 16 which indicates the position of the viewer 5, content packet 1, page mount/content support portion 8 and VPC3 when conformed into a protective storage configuration.

Fig. 5 is an exploded view of viewer 5 which reveals the folded and beveled construction of viewer body 5V which includes apertures 5A. Also revealed are

viewer body 3Y, which is configured with eyepiece apertures 3X and gear pivot pin 3H, which receives gear sleeve 3V of pinion gear 3G so that pinion gear 3G rotates freely in either direction, and meshes with opposing linear gears 3Z and 3T of eyepieces 3J and 3K, respectively. It is annotated that these designated components can be pivotally and
5 slidably secured into place by any number of typical methods, for example, a capping shell which would nest over viewer body 3Y and thus maintain said movable components in the eyepiece well 3W. Also, as illustrated in Fig. 27, viewer body 3Y can be secured to a viewer pivotal chassis (or formed integrally with said same) with any number of techniques. Fig. 36 is mainly concerned with revealing mechanism 5U.

10 Fig. 37 is a front elevational view of mechanism 5U which corresponds with Fig. 36, and portrays the assembled components and the directional motion of said components as they are adjusted to accommodate a user with wide-set eyes. It is understood that the basic mechanical directions and motions portrayed in Fig. 37 can also occur in the opposite directions as indicated so as to achieve interocular adjustment for a
15 narrow eye-setting.

A wide interocular adjustment is achieved when the user grasps eyepiece thumb switch 3S and slides it outward as indicated by arrows 61 and 65. It is understood that the user may grasp either the left or right thumb switch. For this sequential example, the user slides the left switch 3S in the direction indicated by arrow 61, which causes
20 linear gear 3Z to also slide, as indicated by arrow 62, which in turn pivots pinion gear 3G in a clockwise motion around gear pivot pin 3H as indicated by arrow 63, thus driving the meshed teeth of opposing linear gear 3T in the direction indicated by arrow 64, thereby sliding eyepiece 3K in a synchronized manner away from eyepiece 3J, as indicated by arrow 65.

25 Fig. 38 illustrates viewer 7Q and how fulcrum 7P and pivotal arm 7R may be positioned between the lenses 7L and occluding apertures 7I, the pivotal couplings 7N and 7M engaging corresponding means configured with lense carriages 7H and 7U, respectively. These pivotal couplings can be made in a number of techniques common to the mechanical art, nested plastic pins and sockets, rivets, etc. The lense carriages 7H and
30 7U may be integral with the lenses 7L and apertures 7I and may include adjustment switches 7S. The lense carriages are slidably positioned and limited in their movement by positioning apertures 7J, which slidably engage pins 7K; which are integral with base plate

7T, which also integrally includes living hinge 3I and insert plate 7V, shown in section. It is annotated that hinge 3I and plate 7V are shown as one of many possible ways to provide a corresponding means of engaging the viewer to the other components of the present invention, so that the pivotal function of the device as claimed may be achieved; however, the present invention should not be limited to these illustrated means. The advantage of locating the fulcrum and pivotal arm between the lenses is fairly straight forward; this enables adjustment switches 7S to be located on each side of the viewer so it may be adjusted with either hand while viewing.

Fig. 39 depicts book 7O and how 7Q may be configured with insert plate 7V to engage, as indicated by the arrows 80, sleeve 8R of viewer pivotal chassis 8M, which is constructed of fabric with rigid plates sewn within so that the device can maintain its pivotal and support functions. It is understood that once insert plate 7V is slid into position, the viewer pivotal chassis geometry is rendered functional as claimed, and the axes designated as 3I pivot in the same manner as in previous figures.

The pivotal page support 8N, which includes two pivotal axes 3M, also functions as a cover flap and can be releasably secured to 8M with sewn velcro patches or other means common in the art, whereby patch 8I engages patch 8J and 8K engages 8L, respectively.

The content packet 7Y is shown in place, positioned, as shown in Fig. 1, by the packet sheet 7Z being slid into sleeve 8S on the content support portion 8Q, thus determining page pivotal axis 7W.

Stereographic content 7X is thereby positioned to be viewable as depicted in previous figures.

Fig. 40 is an end view of the present invention in a folded storage mode which reveals the components of the present invention.

Whereas the present invention is susceptible of various modifications and alternative constructions, the embodiments suggested in the drawings will herein be described in sufficient detail. It should be understood, however, it is not the intention to limit the invention to the particular forms disclosed, but to indicate the general spacial alignments and inherent geometries and thus define the functional and objective parameters of the present invention.

Claims:

1. A stereographic device comprising
a content support portion configured to position and support stereographic
5 content;
a stereoscopic viewer configured to enable interocular adjustment,
including adjustable left and right viewpoint lense arrangements, and adjustable occluding
apertures configured to enable right stereographic content to be occluded from the left
eye viewpoint and left stereographic content to be occluded from the right eye viewpoint,
10 respectively;
the adjustable lense arrangements and occluding apertures configured to
enable interpupillary alignment relative to the stereographic content positioned and
supported with the content support portion when conformed into a viewing configuration;
a viewer pivotal chassis configured to couple the stereoscopic viewer to
15 the content support portion so that the viewer pivotal chassis is interposed between the
stereoscopic viewer and the content support portion;
the viewer pivotal chassis including a plurality of pivotal axes parallel to an
axis common to the left and right lenses of the stereoscopic viewer;
the viewer pivotal chassis configured with the parallel axes to enable the
20 viewer to be movable in a linear direction perpendicular to the stereoscopic lense axis;
within a focal plane and at a focal length determined by the user, relative and parallel to
the stereographic content positioned with the content support portion when conformed
into a viewing configuration.
2. A modification of the device of claim 1, whereby the content
25 support portion is configured to position and support an axis to enable a plurality of pages
to be pivotable, the axis being parallel to an axis common to the left and right lenses of
the viewer; the pages provided with stereographic content that is viewable with the
viewer when conformed into a viewing configuration.
3. A variation of the device of claim 2, whereby the content support
30 portion is configured to position and support the page axis and the plurality of pages
provided with stereographic content, to thereby enable two pivotally exposed pages,

which are adjacent to and opposite each other and disposed one on each side of the page axis, to be viewable with the viewer when conformed into a viewing configuration.

4. A variation of the device of claim 3, whereby the content support portion includes a pivotable page support surface with at least one pivotable axis parallel and generally adjacent to the page pivotal axis; the surface and axes configured to provide support and facilitate viewing of the pivotally exposed pages with the viewer when conformed into a viewing configuration.

5. A modification of the device of claim 2, whereby the plurality of pivotable pages, each having first and second opposite surfaces provided with stereographic content, the upright direction of the content oriented towards the pivotal axis of the pages; the axis and pages configured for releasable attachment to the content support portion so that the upright content of the first surfaces can be oriented, positioned, viewed with the viewer, released, reoriented and repositioned to enable the upright content of the opposite second surfaces to be viewable with the viewer in a viewing configuration.

6. An adaptation of the device of claim 2, whereby the plurality of pages are configured with transparent sleeves to enable photographic media, including stereographic prints, to be positioned and thereby viewable with the viewer when conformed into a viewing configuration.

7. A modification of the device of claim 1, whereby the content support portion is configured to position, support and releasably engage at least one sheet provided with stereographic content.

8. A variation of the device of claim 1, whereby the content support portion consists of a planar surface provided with stereographic content.

9. A variation of the device of claim 1, whereby the content support portion is configured with a sleeve to slidably receive and thereby position and support a releasably attachable content packet consisting of a plurality of pages configured to be pivotable about an axis, the sleeve enabling the page axis to be positioned parallel to an axis common to the left and right lenses of the viewer, so that the stereographic content provided with the pages is viewable with the viewer when conformed into a viewing configuration.

10. A variation of the stereoscopic viewer of the device of claim 1, whereby the adjustable left and right lenses are configured to enable independent adjustment relative to each other and also relative to the independently adjustable left and right occluding apertures.

5 11. A variation of the stereoscopic viewer of the device of claim 1, whereby the independently adjustable left and right lenses are functionally integrated with the left and right occluding apertures, respectively; so that adjustment of the lenses determines a corresponding adjustment of the occluding apertures.

10 12. A variation of the stereoscopic viewer of the device of claim 1, whereby the adjustable left and right lenses are functionally integrated with the left and right occluding apertures, respectively; so that adjustment of the lenses determines a corresponding adjustment of the occluding apertures; the function of adjustment characterized by synchronized equidistant movement of the left and right lenses and respective occluding apertures towards or away from each other.

15 13. A variation of the stereoscopic viewer of claim 12, whereby the synchronized equidistant movement of the left and right lenses and respective occluding apertures towards or away from each other is enabled with a pivotal arm positioned by a fulcrum, one end of the arm being pivotally coupled to the left lense and occluding aperture, the other end of the pivotal arm being pivotally coupled to the right lense and
20 occluding aperture.

14. A variation of the stereoscopic viewer of claim 12, whereby the synchronized equidistant movement of the left and right lenses and respective occluding apertures toward or away from each other is enabled by rotational movement of a pinion gear meshed with two opposing linear gears, each of which slide on a line parallel to an
25 axis common to the left and right lenses, one of the linear gears being functionally coupled to the left lense and occluding aperture; the other linear gear being functionally coupled to the right lense and occluding aperture.

15. A modification of the device of claim 1, whereby the content support portion, the stereoscopic viewer and the viewer pivotal chassis are pivotally
30 conformable into a storage configuration that interposes the lenses of the stereoscopic viewer in a shielded position between the viewer pivotal chassis and the content support section.

16. A variation of the storage configuration of claim 15, whereby the content support portion, the stereoscopic viewer, and the viewer pivotal chassis are maintained in the storage configuration with releasable fasteners.

17. An improvement of the device of claim 1, whereby the positioned
5 stereographic content is configured to convey to the user of the stereoscopic viewer a visual field of view, including left and right peripheral fields of two-dimensional perception interposed by a central binocular stereo field of three-dimensional perception.

18. An adaptation of the device of claim 7, whereby the sheet is
10 configured with at least one transparent sleeve to position photographic media, including stereographic prints, for viewing with the viewer when conformed into a viewing configuration.

19. An adaptation of the device of claim 9, whereby the plurality of pages of the releasably attachable content packet are configured with transparent sleeves to position photographic media, including stereographic prints.

15 20. A variation of the device of claim 1, whereby the content support portion is configured to position and support a releasably attachable plurality of pages configured to be pivotable about an axis that is parallel to an axis common to the left and right lenses of the viewer, so that the stereographic content provided with the pages is viewable with the viewer when conformed into a viewing configuration.

20 21. An adaptation of the device of claim 20, whereby the plurality of pages are configured with transparent sleeves to be positioned and viewable with the viewer in a viewing configuration to enable photographic media, including stereographic prints.

FIG. 24

8 of 14





FIG. 25







FIG. 26



INTERNATIONAL PRELIMINARY EXAMINATION REPORT

(PCT Article 36 and Rule 70)


Applicant's or agent's file reference 6313-29114	FOR FURTHER ACTION	See Notification of Transmittal of International Preliminary Examination Report (Form PCT/IPEA/416)
International application No. PCT/US97/18028	International filing date (day/month/year) 03 OCTOBER 1997	Priority date (day/month/year) 04 OCTOBER 1996
International Patent Classification (IPC) or national classification and IPC IPC(6): GO2B/27/22 and US Cl.: 359/474, 476, 477, 467		
Applicant CHARLES W. JONES		

1. This international preliminary examination report has been prepared by this International Preliminary Examining Authority and is transmitted to the applicant according to Article 36.
2. This REPORT consists of a total of 4 sheets.
- ☒ This report is also accompanied by ANNEXES, i.e., sheets of the description, claims and/or drawings which have been amended and are the basis for this report and/or sheets containing rectifications made before this Authority. (see Rule 70.16 and Section 607 of the Administrative Instructions under the PCT).

These annexes consist of a total of 9 sheets.

3. This report contains indications relating to the following items:

- I ☒ Basis of the report
- II ☐ Priority
- III ☐ Non-establishment of report with regard to novelty, inventive step or industrial applicability
- IV ☐ Lack of unity of invention
- V ☒ Reasoned statement under Article 35(2) with regard to novelty, inventive step or industrial applicability; citations and explanations supporting such statement
- VI ☐ Certain documents cited
- VII ☐ Certain defects in the international application
- VIII ☐ Certain observations on the international application

Date of submission of the demand 04 MAY 1998	Date of completion of this report 15 JUNE 1998
Name and mailing address of the IPEA/US Commissioner of Patents and Trademarks Box PCT Washington, D.C. 20231 Facsimile No. (703) 305-3230	Authorized officer JON W. HENRY  Telephone No. (703) 305-6106

INTERNATIONAL PRELIMINARY EXAMINATION REPORT

International application No.

PCT/US97/18028

I. Basis of the report

1. This report has been drawn on the basis of *(Substitute sheets which have been furnished to the receiving Office in response to an invitation under Article 14 are referred to in this report as "originally filed" and are not annexed to the report since they do not contain*

☐ the international application as originally filed.

☒ the description, pages (See Attached) , as originally filed.

pages _____ , filed with the demand.

pages _____ , filed with the letter of _____.

pages _____ , filed with the letter of _____.

☒ the claims, Nos. (See Attached) , as originally filed.

Nos. _____ , as amended under Article 19.

Nos. _____ , filed with the demand.

Nos. _____ , filed with the letter of _____.

Nos. _____ , filed with the letter of _____.

☒ the drawings, sheets/~~fig~~ (See Attached) , as originally filed.

sheets/~~fig~~ _____ , filed with the demand.

sheets/~~fig~~ _____ , filed with the letter of _____.

sheets/~~fig~~ _____ , filed with the letter of _____.

2. The amendments have resulted in the cancellation of:

☒ the description, pages NONE .

☒ the claims, Nos. NONE .

☒ the drawings, sheets/~~fig~~ NONE .

3. ☐ This report has been established as if (some of) the amendments had not been made, since they have been considered to go beyond the disclosure as filed, as indicated in the ~~Supplemental Box~~ Additional observations below (Rule 70.2(c)).

4. Additional observations, if necessary:

NONE

INTERNATIONAL PRELIMINARY EXAMINATION REPORT

International application No.

PCT/US97/18028

V. Reasoned statement under Article 35(2) with regard to novelty, inventive step or industrial applicability; citations and explanations supporting such statement**1. STATEMENT**

Novelty (N)	Claims	<u>1-21</u>	YES
	Claims	<u>NONE</u>	NO
Inventive Step (IS)	Claims	<u>1-21</u>	YES
	Claims	<u>NONE</u>	NO
Industrial Applicability (IA)	Claims	<u>1-21</u>	YES
	Claims	<u>NONE</u>	NO

2. CITATIONS AND EXPLANATIONS

Claims 1-21 meet the criteria set out in PCT Article 33(2)-(4), because the prior art does not teach or fairly suggest the stereoscopic device of independent claim 1. Additionally, the claimed invention can be made and/or is useful in industry.

----- NEW CITATIONS -----
NONE

INTERNATIONAL PRELIMINARY EXAMINATION REPORT

International application No.

PCT/US97/18028

Supplemental Box

(To be used when the space in any of the preceding boxes is not sufficient)

Continuation of: Boxes I - VIII

~~Sheet 10~~

I. BASIS OF REPORT:

This report has been drawn on the basis of the description,
pages, 1, 2, 4-7, 9-17, as originally filed.
pages, 3, 8, 18, 19, filed with the demand.
and additional amendments:
NONE

This report has been drawn on the basis of the claims,
numbers, NONE, as originally filed.
numbers, NONE, as amended under Article 19.
numbers, 1-21, filed with the demand.
and additional amendments:
NONE

This report has been drawn on the basis of the drawings,
sheets, 1-13, as originally filed.
sheets, 14, filed with the demand.
and additional amendments:
NONE

full-field-of-view stereographic viewing experience to a wide audience, especially those who do not have access to expensive electronic systems.

One of the key capabilities necessary to achieve this objective is interocular adjustment. The present viewer substantially improves this capability over the previously disclosed and claimed embodiments of this inventor's work as originally filed in U.S. Patent No. 5,499,136, wherein interocular adjustment was achieved by configuring the lenses to be adjustable to the user's individual interpupillary distance, with occluding apertures in a fixed and integral position in the viewer body. This capability is effective to a certain extent, however, it is determined that remarkably improved perception of the immersive image field can be attained by configuring the apertures which frame the left and right images to also be adjustable, to therewith enable right-stereographic content to be occluded from the left eye viewpoint and left-stereographic content to be occluded from the right-eye viewpoint, respectively.

Further, adjustable occluding apertures greatly improve the user's ability to fine-tune and thus see an immersive visual-field that simulates natural vision, with a central stereo-field bordered by left and right peripheral monocular fields. The apertures' close proximity to the user's eyes renders the perception of the shielding edges of the apertures as a soft blur. This soft blur of occlusion is actually very important, because it blends said stereo and mono fields seamlessly together, to create an immersive visual field.

It is annotated that the viewer of the present invention may be configured with any type of lense optics common to the stereoscopic art, including but not limited to the double convex, double convex wedge, plano convex, plano convex wedge, agstigmatic double convex, agstigmatic plano convex, and any other optical lense form or arrangement of lense forms which facilitate optical utilization of the stereoscopic viewer.

Chassis Pivotal Geometries

The pivotal geometries of the chassis portions designated herein as the viewer pivotal chassis (VPC) achieves a substantial improvement over the previous viewer pivotal array (VPA) geometries disclosed in U.S. Patent No. 5,499,136, specifically in embodiments 13C, 14D, and 15E of said patent, which are concerned with enabling the device to achieve a first and second viewing position so that two pivotally-

Fig. 37 is a front elevation view of mechanism 5U which indicates the directional motion of the components during said adjustment.

Fig. 38 is a front elevational view of viewer 7Q, which utilizes a fulcrum and pivotal arm to achieve synchronous lense and aperture adjustment movement in a manner similar to mechanism 5Q of Figs. 33-35, except that the adjustment means of 7Q are disposed between the lenses and apertures.

Fig. 39 is a perspective view of book 70, which portrays viewer 7Q being utilized to create a hybrid stereographic book with a reinforced fabric pivotal chassis and content support portion.

Fig. 40 is an end elevational view of the device of Fig. 39 in a storage configuration.

Detailed Description of the Drawings

Referring to the drawings, Fig. 1 illustrates stereographic book 16 which includes stereoscopic viewer 5. The parallel pivotal axes 3 of the viewer pivotal chassis (VPC) are revealed and pivotally coupled to page mount/content support portion 8 which is configured with sleeve 8A which slidably receives cover 7 of stereographic content packet 1, as indicated by arrows, one of which is designated as 22.

Fig. 2 indicates book 16 in a first viewing position, whereby viewer 5 is aligned and focused as indicated by arrow 21 by the user pivoting VPC3 and page surface 1A which is pivoted on axis 1P, which is established and determined by the engagement of cover 7 of content packet 1 therewith sleeve 8A of page mount/content support portion 8.

Fig. 3 indicates book 16 in a second viewing position whereby the pivotal articulation of VPC3 has shifted to align viewer 5 with page surface 1B. Arrow 23 indicates that the pivotal rotation of the indicated plurality of pages of content packet 1 can be selectively rotated in either direction. It is understood that the stereographic content on page surfaces 1A and 1B is oriented in an upright position relative to viewer 5.

Fig. 4 provides an end elevational view of book 16 which indicates the position of the viewer 5, content packet 1, page mount/content support portion 8 and VPC3 when conformed into a protective storage configuration.

Fig. 5 is an exploded view of viewer 5 which reveals the folded and beveled construction of viewer body 5V which includes apertures 5A. Also revealed are

viewer body 3Y, which is configured with eyepiece apertures 3X and gear pivot pin 3H, which receives gear sleeve 3V of pinion gear 3G so that pinion gear 3G rotates freely in either direction, and meshes with opposing linear gears 3Z and 3T of eyepieces 3J and 3K, respectively. It is annotated that these designated components can be pivotally and
5 slidably secured into place by any number of typical methods, for example, a capping shell which would nest over viewer body 3Y and thus maintain said movable components in the eyepiece well 3W. Also, as illustrated in Fig. 27, viewer body 3Y can be secured to a viewer pivotal chassis (or formed integrally with said same) with any number of techniques. Fig. 36 is mainly concerned with revealing mechanism 5U.

10 Fig. 37 is a front elevational view of mechanism 5U which corresponds with Fig. 36, and portrays the assembled components and the directional motion of said components as they are adjusted to accommodate a user with wide-set eyes. It is understood that the basic mechanical directions and motions portrayed in Fig. 37 can also occur in the opposite directions as indicated so as to achieve interocular adjustment for a
15 narrow eye-setting.

A wide interocular adjustment is achieved when the user grasps eyepiece thumb switch 3S and slides it outward as indicated by arrows 61 and 65. It is understood that the user may grasp either the left or right thumb switch. For this sequential example, the user slides the left switch 3S in the direction indicated by arrow 61, which causes
20 linear gear 3Z to also slide, as indicated by arrow 62, which in turn pivots pinion gear 3G in a clockwise motion around gear pivot pin 3H as indicated by arrow 63, thus driving the meshed teeth of opposing linear gear 3T in the direction indicated by arrow 64, thereby sliding eyepiece 3K in a synchronized manner away from eyepiece 3J, as indicated by arrow 65.

25 Fig. 38 illustrates how fulcrum 7P and pivotal arm 7R may be positioned between the lenses 7L and occluding apertures 7I, the pivotal couplings 7N and 7M engaging corresponding means configured with lense carriages 7H and 7U, respectively. These pivotal couplings can be made in a number of techniques common to the mechanical art, nested plastic pins and sockets, rivets, etc. The lense carriages 7H and 7U
30 may be integral with the lenses 7L and apertures 7I and may include adjustment switches 7S. The lense carriages are slidably positioned and limited in their movement by positioning apertures 7J, which slidably engage pins 7K, which are integral with base plate

7T, which also integrally includes living hinge 3I and insert plate 7V, shown in section. It is annotated that hinge 3I and plate 7V are shown as one of many possible ways to provide a corresponding means of engaging the viewer to the other components of the present invention, so that the pivotal function of the device as claimed may be achieved; however, the present invention should not be limited to these illustrated means. The advantage of locating the fulcrum and pivotal arm between the lenses is fairly straight forward; this enables adjustment switches 7S to be located on each side of the viewer so it may be adjusted with either hand while viewing.

Fig. 39 depicts book 7O and how 7Q may be configured with insert plate 7V to engage, as indicated by the arrows 80, sleeve 8N of viewer pivotal chassis 8M, which is constructed of fabric with rigid plates sewn within so that the device can maintain its pivotal and support functions. It is understood that once insert plate 7V is slid into position, the viewer pivotal chassis geometry is rendered functional as claimed, and the axes designated as 3I pivot in the same manner as in previous figures.

The pivotal page support 8N, which includes two pivotal axes 3M, also functions as a cover flap and can be releasably secured to 8M with sewn velcro patches or other means common in the art, whereby patch 8I engages patch 8J and 8K engages 8L, respectively.

The content packet 7Y is shown in place, positioned, as shown in Fig. 1, by the packet sheet 7Y being slid into sleeve 8S on the content support portion 8Q, thus determining page pivotal axis 7W.

Stereographic content 7X is thereby positioned to be viewable as depicted in previous figures.

Fig. 40 is an end view of the present invention in a folded storage mode which reveals the components of the present invention.

Whereas the present invention is susceptible of various modifications and alternative constructions, the embodiments suggested in the drawings will herein be described in sufficient detail. It should be understood, however, it is not the intention to limit the invention to the particular forms disclosed, but to indicate the general spacial alignments and inherent geometries and thus define the functional and objective parameters of the present invention.

Claims:

1. A stereographic device comprising
a content support portion configured with means to position and support
5 stereographic content;
stereographic content positioned and supported with the content support
portion;
a stereoscopic viewer configured with means to enable interocular
adjustment, including adjustable left and right viewpoint lense arrangements, and
10 adjustable occluding apertures configured to enable right stereographic content to be
occluded from the left eye viewpoint and left stereographic content to be occluded from
the right eye viewpoint, respectively;
the adjustable lense arrangements and occluding apertures configured to
enable interpupillary alignment relative to the stereographic content positioned and
15 supported with the content support portion when conformed into a viewing configuration;
a viewer pivotal chassis configured with corresponding means to couple
the means of the stereoscopic viewer to the content support portion so that the viewer
pivotal chassis is interposed between the stereoscopic viewer and the content support
portion;
20 the viewer pivotal chassis including a plurality of pivotal axes parallel to an
axis common to the left and right lenses of the stereoscopic viewer;
the viewer pivotal chassis configured with the parallel axes to enable the
viewer to be movable in a linear direction perpendicular to the stereoscopic lense axis;
within a focal plane and at a focal length determined by the user, relative and parallel to
25 the stereographic content provided with the content support portion when conformed into
a viewing configuration.
2. A modification of the device of claim 1, whereby the content
support portion is configured with means to position and support an axis to enable a
plurality of pages to be pivotable, the axis being parallel to an axis common to the left and
30 right lenses of the viewer; the pages provided with stereographic content that is viewable
with the viewer when conformed into a viewing configuration.

3. A variation of the device of claim 2, whereby the content support portion is configured to position and support the page axis and the plurality of pages provided with stereographic content, to thereby enable two pivotally exposed pages, which are adjacent to and opposite each other and disposed one on each side of the page axis, to be viewable with the viewer when conformed into a viewing configuration.

4. A variation of the device of claim 3, whereby the content support portion includes a pivotable page support surface with at least one pivotable axis parallel and generally adjacent to the page pivotal axis; the surface and axes configured to provide support and facilitate viewing of the pivotally exposed pages with the viewer when conformed into a viewing configuration.

5. A modification of the device of claim 2, whereby the plurality of pivotable pages, each having first and second opposite surfaces, are provided therewith stereographic content, the upright direction of the content oriented towards the pivotal axis of the pages, the axis provided with releasably attachable corresponding means to engage the content support portion, to enable the upright content of the first surfaces to be attachable to the content support portion and thereby viewable with the viewer, released, reoriented and reattached to enable the upright content of the second surfaces to be viewable with the viewer in a viewing conformation.

6. An adaptation of the device of claim 2, whereby the plurality of pages are configured to convey photographic media, including stereographic prints, one of the means of page configuration including transparent sleeves to enable photographic media to be positioned, supported and thereby viewable with the viewer when conformed into a viewing configuration.

7. A modification of the device of claim 1, whereby the content support portion is configured to position, support and releasably engage at least one sheet provided with stereographic content.

8. A variation of the device of claim 1, whereby the content support portion consists of a planar surface provided with stereographic content.

9. A variation of the device of claim 1, whereby the content support portion is configured with a sleeve to slidably receive and thereby position and support a releasably attachable content packet consisting of a plurality of pages configured to be pivotable about an axis, the sleeve enabling the page axis to be positioned parallel to an

axis common to the left and right lenses of the viewer, so that the stereographic content provided with the pages is viewable with the viewer when conformed into a viewing configuration.

10. A variation of the stereographic viewer of the device of claim 1,
5 whereby the means of the adjustable left and right lenses are configured to enable independent adjustment relative to each other and also relative to the means of the independently adjustable left and right occluding apertures.

11. A variation of the stereoscopic viewer of the device of claim 1,
10 whereby the means of the independently adjustable left and right lenses are functionally integrated with the left and right occluding apertures, respectively; so that adjustment of the lenses determines a corresponding adjustment of the occluding apertures.

12. A variation of the stereoscopic viewer of the device of claim 1,
15 whereby the adjustable left and right lenses are functionally integrated with the left and right occluding apertures, respectively; so that adjustment of the lenses determines a corresponding adjustment of the occluding apertures; the function of adjustment enabled with means that synchronize equidistant movement of the left and right lenses and respective occluding apertures towards or away from each other.

13. A variation of the stereoscopic viewer of claim 12, whereby the
20 synchronized equidistant movement of the left and right lenses and respective occluding apertures towards or away from each other is enabled with the means of a pivotal arm positioned by a fulcrum, one end of the arm being pivotally coupled to the means of the left lense and occluding aperture, the other end of the pivotal arm being pivotally coupled to the means of the right lense and occluding aperture.

14. A variation of the stereoscopic viewer of claim 12, whereby the
25 synchronized equidistant movement of the left and right lenses and respective occluding apertures toward or away from each other is enabled by rotational movement of a pinion gear meshed with two opposing linear gears, each of which slide on an axis parallel to an axis common to the left and right lenses, one of the linear gears being functionally coupled to the means of the left lense and occluding aperture; the other linear gear being
30 functionally coupled to the means of the right lense and occluding aperture.

15. A modification of the device of claim 1, whereby the content
support portion, the stereoscopic viewer and the viewer pivotal chassis are pivotally

conformable into a storage configuration that interposes the lenses of the stereoscopic viewer in a shielded position between the viewer pivotal chassis and the content support section.

5 16. A variation of the storage configuration of claim 15, whereby the content support portion, the stereoscopic viewer, and the viewer pivotal chassis are maintained in the storage configuration with corresponding, releasable fastening means.

10 17. An improvement of the device of claim 1, whereby the stereographic content provided with the content support portion is configured to convey to the user, with the means of the stereoscopic viewer when conformed into a viewing configuration, a visual field of view, including left and right peripheral fields of two-dimensional perception interposed by a central binocular stereo field of three-dimensional perception.

14 of 14
FIG. 38




FIG. 39





FIG. 40



PATENT COOPERATION TREATY

1600

From the
INTERNATIONAL PRELIMINARY EXAMINING AUTHORITY

PCT

To: TIMOTHY E. NIEDNAGEL
BARNES & THORNBURG
11 SOUTH MERIDIAN STREET
INDIANAPOLIS, INDIANA 46204

RECEIVED

AUG 04 1998

BARNES & THORNBURG

NOTIFICATION OF TRANSMITTAL OF INTERNATIONAL PRELIMINARY EXAMINATION REPORT

(PCT Rule 71.1)

Date of Mailing
(day/month/year) **29 JUL 1998**

Applicant's or agent's file reference
6313-29114

IMPORTANT NOTIFICATION

International application No.
PCT/US97/18028

International filing date (day/month/year)
03 OCTOBER 1997

Priority Date (day/month/year)
04 OCTOBER 1996

Applicant
CHARLES W. JONES

1. The applicant is hereby notified that this International Preliminary Examining Authority transmits herewith the international preliminary examination report and its annexes, if any, established on the international application.
2. A copy of the report and its annexes, if any, is being transmitted to the International Bureau for communication to all the elected Offices.
3. Where required by any of the elected Offices, the International Bureau will prepare an English translation of the report (but not of any annexes) and will transmit such translation to those Offices.

4. REMINDER

The applicant must enter the national phase before each elected Office by performing certain acts (filing translations and paying national fees) within 30 months from the priority date (or later in some Offices)(Article 39(1))(see also the reminder sent by the International Bureau with Form PCT/IB/301).

Where a translation of the international application must be furnished to an elected Office, that translation must contain a translation of any annexes to the international preliminary examination report. It is the applicant's responsibility to prepare and furnish such translation directly to each elected Office concerned.

For further details on the applicable time limits and requirements of the elected Offices, see Volume II of the PCT Applicant's Guide.

Name and mailing address of the IPEA/US
Commissioner of Patents and Trademarks
Box PCT
Washington, D.C. 20231

Facsimile No. (703) 305-3230

Authorized officer

JON W. HENRY

Telephone No. (703) 305-6106

PATENT COOPERATION TREATY

PCT

INTERNATIONAL PRELIMINARY EXAMINATION REPORT


(PCT Article 36 and Rule 70)

Applicant's or agent's file reference 6313-29114	FOR FURTHER ACTION See Notification of Transmittal of International Preliminary Examination Report (Form PCT/IPEA/416)	
International application No. PCT/US97/18028	International filing date (day/month/year) 03 OCTOBER 1997	Priority date (day/month/year) 04 OCTOBER 1996
International Patent Classification (IPC) or national classification and IPC IPC(6): GO2B/27/22 and US Cl.: 359/474, 476, 477, 467		
Applicant CHARLES W. JONES		

1. This international preliminary examination report has been prepared by this International Preliminary Examining Authority and is transmitted to the applicant according to Article 36.
2. This REPORT consists of a total of 4 sheets.
☒ This report is also accompanied by ANNEXES, i.e., sheets of the description, claims and/or drawings which have been amended and are the basis for this report and/or sheets containing rectifications made before this Authority. (see Rule 70.16 and Section 607 of the Administrative Instructions under the PCT).
 These annexes consist of a total of 9 sheets.

3. This report contains indications relating to the following items:

- I ☒ Basis of the report
- II ☐ Priority
- III ☐ Non-establishment of report with regard to novelty, inventive step or industrial applicability
- IV ☐ Lack of unity of invention
- V ☒ Reasoned statement under Article 35(2) with regard to novelty, inventive step or industrial applicability; citations and explanations supporting such statement
- VI ☐ Certain documents cited
- VII ☐ Certain defects in the international application
- VIII ☐ Certain observations on the international application

Date of submission of the demand 04 MAY 1998	Date of completion of this report 15 JUNE 1998
Name and mailing address of the IPEA/US Commissioner of Patents and Trademarks Box PCT Washington, D.C. 20231 Facsimile No. (703) 305-3230	Authorized officer JON W. HENRY  Telephone No. (703) 305-6106

INTERNATIONAL PRELIMINARY EXAMINATION REPORT

International application No.

PCT/US97/18028

I. Basis of the report

1. This report has been drawn on the basis of *(Substitute sheets which have been furnished to the receiving Office in response to an invitation under Article 14 are referred to in this report as "originally filed" and are not annexed to the report since they do not contain*

☐ the international application as originally filed.

☒ the description, pages (See Attached) , as originally filed.

pages _____ , filed with the demand.

pages _____ , filed with the letter of _____.

pages _____ , filed with the letter of _____.

☒ the claims, Nos. (See Attached) , as originally filed.

Nos. _____ , as amended under Article 19.

Nos. _____ , filed with the demand.

Nos. _____ , filed with the letter of _____.

Nos. _____ , filed with the letter of _____.

☒ the drawings, sheets/fig (See Attached) , as originally filed.

sheets/fig _____ , filed with the demand.

sheets/fig _____ , filed with the letter of _____.

sheets/fig _____ , filed with the letter of _____.

2. The amendments have resulted in the cancellation of:

☒ the description, pages NONE .

☒ the claims, Nos. NONE .

☒ the drawings, sheets/fig NONE .

3. ☐ This report has been established as if (some of) the amendments had not been made, since they have been considered to go beyond the disclosure as filed, as indicated in the ~~Supplemental Box~~ Additional observations below (Rule 70.2(c)).

4. Additional observations, if necessary:

NONE

INTERNATIONAL PRELIMINARY EXAMINATION REPORT

International application No.

PCT/US97/18028

V. Reasoned statement under Article 35(2) with regard to novelty, inventive step or industrial applicability; citations and explanations supporting such statement**1. STATEMENT**

Novelty (N)

Claims	<u>1-21</u>	YES
Claims	<u>NONE</u>	NO

Inventive Step (IS)

Claims	<u>1-21</u>	YES
Claims	<u>NONE</u>	NO

Industrial Applicability (IA)

Claims	<u>1-21</u>	YES
Claims	<u>NONE</u>	NO

2. CITATIONS AND EXPLANATIONS

Claims 1-21 meet the criteria set out in PCT Article 33(2)-(4), because the prior art does not teach or fairly suggest the stereoscopic device of independent claim 1. Additionally, the claimed invention can be made and/or is useful in industry.

----- NEW CITATIONS -----
NONE

Supplemental Box

(To be used when the space in any of the preceding boxes is not sufficient)

Continuation of: Boxes I - VIII

Sheet 10

I. BASIS OF REPORT:

This report has been drawn on the basis of the description,
pages, 1, 2, 4-7, 9-17, as originally filed.
pages, 3, 8, 18, 19, filed with the demand.
and additional amendments:
NONE

This report has been drawn on the basis of the claims,
numbers, NONE, as originally filed.
numbers, NONE, as amended under Article 19.
numbers, 1-21, filed with the demand.
and additional amendments:
NONE

This report has been drawn on the basis of the drawings,
sheets, 1-13, as originally filed.
sheets, 14, filed with the demand.
and additional amendments:
NONE

-3-

full-field-of-view stereographic viewing experience to a wide audience, especially those who do not have access to expensive electronic systems.

One of the key capabilities necessary to achieve this objective is interocular adjustment. The present viewer substantially improves this capability over the previously disclosed and claimed embodiments of this inventor's work as originally filed in U.S. Patent No. 5,499,136, wherein interocular adjustment was achieved by configuring the lenses to be adjustable to the user's individual interpupillary distance, with occluding apertures in a fixed and integral position in the viewer body. This capability is effective to a certain extent, however, it is determined that remarkably improved perception of the immersive image field can be attained by configuring the apertures which frame the left and right images to also be adjustable, to therewith enable right-stereographic content to be occluded from the left eye viewpoint and left-stereographic content to be occluded from the right-eye viewpoint, respectively.

Further, adjustable occluding apertures greatly improve the user's ability to fine-tune and thus see an immersive visual-field that simulates natural vision, with a central stereo-field bordered by left and right peripheral monocular fields. The apertures' close proximity to the user's eyes renders the perception of the shielding edges of the apertures as a soft blur. This soft blur of occlusion is actually very important, because it blends said stereo and mono fields seamlessly together, to create an immersive visual field.

It is annotated that the viewer of the present invention may be configured with any type of lense optics common to the stereoscopic art, including but not limited to the double convex, double convex wedge, plano convex, plano convex wedge, anastigmatic and any other optical lense form or arrangement of lense forms which facilitate optical utilization of the stereoscopic viewer.

Chassis Pivotal Geometries

The pivotal geometries of the chassis portions designated herein as the viewer pivotal chassis (VPC) achieves a substantial improvement over the previous viewer pivotal array (VPA) geometries disclosed in U.S. Patent No. 5,499,136, specifically in embodiments 13C, 14D, and 15E of said patent, which are concerned with enabling the device to achieve a first and second viewing position so that two pivotally-

AMENDED SHEET

-8-

Fig. 37 is a front elevation view of mechanism 5U which indicates the directional motion of the components during said adjustment.

Fig. 38 is a front elevational view of viewer 7Q, which utilizes a fulcrum and pivotal arm to achieve synchronous lense and aperture adjustment movement in a manner similar to mechanism 5Q of Figs. 33-35, except that the adjustment means of 7Q are interposed between the lenses and apertures.

Fig. 39 is a perspective view of book 70, which portrays viewer 7Q being utilized to create a hybrid stereographic book with a reinforced fabric pivotal chassis and content support portion.

Fig. 40 is an end elevational view of the device of Fig. 39 in a storage configuration.

Detailed Description of the Drawings

Referring to the drawings, Fig. 1 illustrates stereographic book 16 which includes stereoscopic viewer 5. The parallel pivotal axes 3 of the viewer pivotal chassis (VPC) are revealed and pivotally coupled to page mount/content support portion 8 which is configured with sleeve 8A which slidably receives cover 7 of stereographic content packet 1, as indicated by arrows, one of which is designated as 22.

Fig. 2 indicates book 16 in a first viewing position, whereby viewer 5 is aligned and focused as indicated by arrow 21 by the user pivoting VPC3 and page surface 1A which is pivoted on axis 1P, which is established and determined by the engagement of cover 7 of content packet 1 therewith sleeve 8A of page mount/content support portion 8.

Fig. 3 indicates book 16 in a second viewing position whereby the pivotal articulation of VPC3 has shifted to align viewer 5 with page surface 1B. Arrow 23 indicates that the pivotal rotation of the indicated plurality of pages of content packet 1 can be selectively rotated in either direction. It is understood that the stereographic content on page surfaces 1A and 1B is oriented in an upright position relative to viewer 5.

Fig. 4 provides an end elevational view of book 16 which indicates the position of the viewer 5, content packet 1, page mount/content support portion 8 and VPC3 when conformed into a protective storage configuration.

Fig. 5 is an exploded view of viewer 5 which reveals the folded and beveled construction of viewer body 5V which includes apertures 5A. Also revealed are

-18-

viewer body 3Y, which is configured with eyepiece apertures 3X and gear pivot pin 3H, which receives gear sleeve 3V of pinion gear 3G so that pinion gear 3G rotates freely in either direction, and meshes with opposing linear gears 3Z and 3T of eyepieces 3J and 3K, respectively. It is annotated that these designated components can be pivotally and
5 slidably secured into place by any number of typical methods, for example, a capping shell which would nest over viewer body 3Y and thus maintain said movable components in the eyepiece well 3W. Also, as illustrated in Fig. 27, viewer body 3Y can be secured to a viewer pivotal chassis (or formed integrally with said same) with any number of techniques. Fig. 36 is mainly concerned with revealing mechanism 5U.

10 Fig. 37 is a front elevational view of mechanism 5U which corresponds with Fig. 36, and portrays the assembled components and the directional motion of said components as they are adjusted to accommodate a user with wide-set eyes. It is understood that the basic mechanical directions and motions portrayed in Fig. 37 can also occur in the opposite directions as indicated so as to achieve interocular adjustment for a
15 narrow eye-setting.

A wide interocular adjustment is achieved when the user grasps eyepiece thumb switch 3S and slides it outward as indicated by arrows 61 and 65. It is understood that the user may grasp either the left or right thumb switch. For this sequential example, the user slides the left switch 3S in the direction indicated by arrow 61, which causes
20 linear gear 3Z to also slide, as indicated by arrow 62, which in turn pivots pinion gear 3G in a clockwise motion around gear pivot pin 3H as indicated by arrow 63, thus driving the meshed teeth of opposing linear gear 3T in the direction indicated by arrow 64, thereby sliding eyepiece 3K in a synchronized manner away from eyepiece 3J, as indicated by arrow 65.

25 Fig. 38 illustrates viewer 7Q and how fulcrum 7P and pivotal arm 7R may be positioned between the lenses 7L and occluding apertures 7I, the pivotal couplings 7N and 7M engaging corresponding means configured with lense carriages 7H and 7U, respectively. These pivotal couplings can be made in a number of techniques common to the mechanical art, nested plastic pins and sockets, rivets, etc. The lense carriages 7H and
30 7U may be integral with the lenses 7L and apertures 7I and may include adjustment switches 7S. The lense carriages are slidably positioned and limited in their movement by positioning apertures 7J, which slidably engage pins 7K; which are integral with base plate

AMENDED SHEET

-19-

7T, which also integrally includes living hinge 3I and insert plate 7V, shown in section. It is annotated that hinge 3I and plate 7V are shown as one of many possible ways to provide a corresponding means of engaging the viewer to the other components of the present invention, so that the pivotal function of the device as claimed may be achieved; however, the present invention should not be limited to these illustrated means. The advantage of locating the fulcrum and pivotal arm between the lenses is fairly straight forward; this enables adjustment switches 7S to be located on each side of the viewer so it may be adjusted with either hand while viewing.

Fig. 39 depicts book 7O and how 7Q may be configured with insert plate 7V to engage, as indicated by the arrows 80, sleeve 8R of viewer pivotal chassis 8M, which is constructed of fabric with rigid plates sewn within so that the device can maintain its pivotal and support functions. It is understood that once insert plate 7V is slid into position, the viewer pivotal chassis geometry is rendered functional as claimed, and the axes designated as 3I pivot in the same manner as in previous figures.

The pivotal page support 8N, which includes two pivotal axes 3M, also functions as a cover flap and can be releasably secured to 8M with sewn velcro patches or other means common in the art, whereby patch 8I engages patch 8J and 8K engages 8L, respectively.

The content packet 7Y is shown in place, positioned, as shown in Fig. 1, by the packet sheet 7Z being slid into sleeve 8S on the content support portion 8Q, thus determining page pivotal axis 7W.

Stereographic content 7X is thereby positioned to be viewable as depicted in previous figures.

Fig. 40 is an end view of the present invention in a folded storage mode which reveals the components of the present invention.

Whereas the present invention is susceptible of various modifications and alternative constructions, the embodiments suggested in the drawings will herein be described in sufficient detail. It should be understood, however, it is not the intention to limit the invention to the particular forms disclosed, but to indicate the general spacial alignments and inherent geometries and thus define the functional and objective parameters of the present invention.

AMENDED SHEET

-20-

Claims:

1. A stereographic device comprising
a content support portion configured to position and support stereographic
5 content;
a stereoscopic viewer configured to enable interocular adjustment,
including adjustable left and right viewpoint lense arrangements, and adjustable occluding
apertures configured to enable right stereographic content to be occluded from the left
eye viewpoint and left stereographic content to be occluded from the right eye viewpoint,
10 respectively;
the adjustable lense arrangements and occluding apertures configured to
enable interpupillary alignment relative to the stereographic content positioned and
supported with the content support portion when conformed into a viewing configuration;
a viewer pivotal chassis configured to couple the stereoscopic viewer to
15 the content support portion so that the viewer pivotal chassis is interposed between the
stereoscopic viewer and the content support portion;
the viewer pivotal chassis including a plurality of pivotal axes parallel to an
axis common to the left and right lenses of the stereoscopic viewer;
the viewer pivotal chassis configured with the parallel axes to enable the
20 viewer to be movable in a linear direction perpendicular to the stereoscopic lense axis;
within a focal plane and at a focal length determined by the user, relative and parallel to
the stereographic content positioned with the content support portion when conformed
into a viewing configuration.
2. A modification of the device of claim 1, whereby the content
25 support portion is configured to position and support an axis to enable a plurality of pages
to be pivotable, the axis being parallel to an axis common to the left and right lenses of
the viewer; the pages provided with stereographic content that is viewable with the
viewer when conformed into a viewing configuration.
3. A variation of the device of claim 2, whereby the content support
30 portion is configured to position and support the page axis and the plurality of pages
provided with stereographic content, to thereby enable two pivotally exposed pages,

-21-

which are adjacent to and opposite each other and disposed one on each side of the page axis, to be viewable with the viewer when conformed into a viewing configuration.

4. A variation of the device of claim 3, whereby the content support portion includes a pivotable page support surface with at least one pivotable axis parallel and generally adjacent to the page pivotal axis; the surface and axes configured to provide support and facilitate viewing of the pivotally exposed pages with the viewer when conformed into a viewing configuration.

5. A modification of the device of claim 2, whereby the plurality of pivotable pages, each having first and second opposite surfaces provided with stereographic content, the upright direction of the content oriented towards the pivotal axis of the pages; the axis and pages configured for releasable attachment to the content support portion so that the upright content of the first surfaces can be oriented, positioned, viewed with the viewer, released, reoriented and repositioned to enable the upright content of the opposite second surfaces to be viewable with the viewer in a viewing configuration.

6. An adaptation of the device of claim 2, whereby the plurality of pages are configured with transparent sleeves to enable photographic media, including stereographic prints, to be positioned and thereby viewable with the viewer when conformed into a viewing configuration.

7. A modification of the ~~device~~ of claim 1, whereby the content support portion is configured to position, support and releasably engage at least one sheet provided with stereographic content.

8. A variation of the device of claim 1, whereby the content support portion consists of a planar surface provided with stereographic content.

9. A variation of the device of claim 1, whereby the content support portion is configured with a sleeve to slidably receive and thereby position and support a releasably attachable content packet consisting of a plurality of pages configured to be pivotable about an axis, the sleeve enabling the page axis to be positioned parallel to an axis common to the left and right lenses of the viewer, so that the stereographic content provided with the pages is viewable with the viewer when conformed into a viewing configuration.

10. A variation of the stereoscopic viewer of the device of claim 1, whereby the adjustable left and right lenses are configured to enable independent adjustment relative to each other and also relative to the independently adjustable left and right occluding apertures.

5 11. A variation of the stereoscopic viewer of the device of claim 1, whereby the independently adjustable left and right lenses are functionally integrated with the left and right occluding apertures, respectively; so that adjustment of the lenses determines a corresponding adjustment of the occluding apertures.

10 12. A variation of the stereoscopic viewer of the device of claim 1, whereby the adjustable left and right lenses are functionally integrated with the left and right occluding apertures, respectively; so that adjustment of the lenses determines a corresponding adjustment of the occluding apertures; the function of adjustment characterized by synchronized equidistant movement of the left and right lenses and respective occluding apertures towards or away from each other.

15 13. A variation of the stereoscopic viewer of claim 12, whereby the synchronized equidistant movement of the left and right lenses and respective occluding apertures towards or away from each other is enabled with a pivotal arm positioned by a fulcrum, one end of the arm being pivotally coupled to the left lense and occluding aperture, the other end of the pivotal arm being pivotally coupled to the right lense and
20 occluding aperture.

14. A variation of the stereoscopic viewer of claim 12, whereby the synchronized equidistant movement of the left and right lenses and respective occluding apertures toward or away from each other is enabled by rotational movement of a pinion gear meshed with two opposing linear gears, each of which slide on a line parallel to an
25 axis common to the left and right lenses, one of the linear gears being functionally coupled to the left lense and occluding aperture; the other linear gear being functionally coupled to the right lense and occluding aperture.

15. A modification of the device of claim 1, whereby the content support portion, the stereoscopic viewer and the viewer pivotal chassis are pivotally
30 conformable into a storage configuration that interposes the lenses of the stereoscopic viewer in a shielded position between the viewer pivotal chassis and the content support section.

-23-

16. A variation of the storage configuration of claim 15, whereby the content support portion, the stereoscopic viewer, and the viewer pivotal chassis are maintained in the storage configuration with releasable fasteners.

5 17. An improvement of the device of claim 1, whereby the positioned stereographic content is configured to convey to the user of the stereoscopic viewer a visual field of view, including left and right peripheral fields of two-dimensional perception interposed by a central binocular stereo field of three-dimensional perception.




10 18. An adaptation of the device of claim 7, whereby the sheet is configured with at least one transparent sleeve to position photographic media, including stereographic prints, for viewing with the viewer when conformed into a viewing configuration.

19. An adaptation of the device of claim 9, whereby the plurality of pages of the releasably attachable content packet are configured with transparent sleeves to position photographic media, including stereographic prints.

15 20. A variation of the device of claim 1, whereby the content support portion is configured to position and support a releasably attachable plurality of pages configured to be pivotable about an axis that is parallel to an axis common to the left and right lenses of the viewer, so that the stereographic content provided with the pages is viewable with the viewer when conformed into a viewing configuration.

20 21. An adaptation of the device of claim 20, whereby the plurality of pages are configured with transparent sleeves to be positioned and viewable with the viewer in a viewing configuration to enable photographic media, including stereographic prints.

AMENDED SHEET



PCT

REQUEST

The undersigned requests that the present international application be processed according to the Patent Cooperation Treaty.

For receiving Office use only

International Application No.

International Filing Date

Name of receiving Office and "PCT International Application"

Applicant's or agent's file reference
(if desired) (12 characters maximum) 6313-29114

Box No. I TITLE OF INVENTION
STEREOGRAPHIC BOOK

Box No. II APPLICANT

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (i.e. country) of residence if no State of residence is indicated below.)

JONES, Charles W.
P.O. Box 161
Knightstown, Indiana 46148
US

☒ This person is also inventor.

Telephone No.
None

Facsimile No.
None

Teleprinter No.

State (i.e. country) of nationality:
US

State (i.e. country) of residence:
US

This person is applicant for the purposes of: ☒ all designated States ☐ all designated States except the United States of America ☐ the United States of America only ☐ the States indicated in the Supplemental Box

Box No. III FURTHER APPLICANT(S) AND/OR (FURTHER) INVENTOR(S)

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (i.e. country) of residence if no State of residence is indicated below.)

This person is:

- ☐ applicant only
☐ applicant and inventor
☐ inventor only (If this check-box is marked, do not fill in below.)

State (i.e. country) of nationality:

State (i.e. country) of residence:

This person is applicant for the purposes of: ☐ all designated States ☐ all designated States except the United States of America ☐ the United States of America only ☐ the States indicated in the Supplemental Box

☐ Further applicants and/or (further) inventors are indicated on a continuation sheet.

Box No. IV AGENT OR COMMON REPRESENTATIVE; OR ADDRESS FOR CORRESPONDENCE

The person identified below is hereby has been appointed to act on behalf of the applicant(s) before the competent International Authorities as:

☒ agent ☐ common representative

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country.)

NIEDNAGEL, Timothy E.
BARNES & THORNBURG
11 South Meridian Street
Indianapolis, Indiana 46204
US

Telephone No.

(317) 236-1313

Facsimile No.

(317) 231-7433

Teleprinter No.

☐ Mark this check-box where no agent or common representative is has been appointed and the space above is used instead to indicate a special address to which correspondence should be sent.

Box No.V DESIGNATION OF STATES

The following designations are hereby made under Rule 4.9(a) (mark the applicable check-boxes; at least one must be marked):

Regional Patent

- ☐ AP ARIPO Patent: GH Ghana, KE Kenya, LS Lesotho, MW Malawi, SD Sudan, SZ Swaziland, UG Uganda, ZW Zimbabwe, and any other State which is a Contracting State of the Harare Protocol and of the PCT
- ☐ EA Eurasian Patent: AM Armenia, AZ Azerbaijan, BY Belarus, KG Kyrgyzstan, KZ Kazakhstan, MD Republic of Moldova, RU Russian Federation, TJ Tajikistan, TM Turkmenistan, and any other State which is a Contracting State of the Eurasian Patent Convention and of the PCT
- ☒ EP European Patent: AT Austria, BE Belgium, CH and LI Switzerland and Liechtenstein, DE Germany, DK Denmark, ES Spain, FI Finland, FR France, GB United Kingdom, GR Greece, IE Ireland, IT Italy, LU Luxembourg, MC Monaco, NL Netherlands, PT Portugal, SE Sweden, and any other State which is a Contracting State of the European Patent Convention and of the PCT
- ☐ OA OAPI Patent: BF Burkina Faso, BJ Benin, CF Central African Republic, CG Congo, CI Côte d'Ivoire, CM Cameroon, GA Gabon, GN Guinea, ML Mali, MR Mauritania, NE Niger, SN Senegal, TD Chad, TG Togo, and any other State which is a member State of OAPI and a Contracting State of the PCT (if other kind of protection or treatment desired, specify on dotted line)

National Patent (if other kind of protection or treatment desired, specify on dotted line):

- | | |
|---|---|
| <input type="checkbox"/> AL Albania | <input type="checkbox"/> LV Latvia |
| <input type="checkbox"/> AM Armenia | <input type="checkbox"/> MD Republic of Moldova |
| <input type="checkbox"/> AT Austria | <input type="checkbox"/> MG Madagascar |
| <input type="checkbox"/> AU Australia | <input type="checkbox"/> MK The former Yugoslav Republic of Macedonia |
| <input type="checkbox"/> AZ Azerbaijan | |
| <input type="checkbox"/> BA Bosnia and Herzegovina | <input type="checkbox"/> MN Mongolia |
| <input type="checkbox"/> BB Barbados | <input type="checkbox"/> MW Malawi |
| <input type="checkbox"/> BG Bulgaria | <input type="checkbox"/> MX Mexico |
| <input type="checkbox"/> BR Brazil | <input type="checkbox"/> NO Norway |
| <input type="checkbox"/> BY Belarus | <input type="checkbox"/> NZ New Zealand |
| <input checked="" type="checkbox"/> CA Canada | <input type="checkbox"/> PL Poland |
| <input type="checkbox"/> CH and LI Switzerland and Liechtenstein | <input type="checkbox"/> PT Portugal |
| <input type="checkbox"/> CN China | <input type="checkbox"/> RO Romania |
| <input type="checkbox"/> CU Cuba | <input type="checkbox"/> RU Russian Federation |
| <input type="checkbox"/> CZ Czech Republic | <input type="checkbox"/> SD Sudan |
| <input type="checkbox"/> DE Germany | <input type="checkbox"/> SE Sweden |
| <input type="checkbox"/> DK Denmark | <input type="checkbox"/> SG Singapore |
| <input type="checkbox"/> EE Estonia | <input type="checkbox"/> SI Slovenia |
| <input type="checkbox"/> ES Spain | <input type="checkbox"/> SK Slovakia |
| <input type="checkbox"/> FI Finland | <input type="checkbox"/> SL Sierra Leone |
| <input type="checkbox"/> GB United Kingdom | <input type="checkbox"/> TJ Tajikistan |
| <input type="checkbox"/> GE Georgia | <input type="checkbox"/> TM Turkmenistan |
| <input type="checkbox"/> GH Ghana | <input type="checkbox"/> TR Turkey |
| <input type="checkbox"/> HU Hungary | <input type="checkbox"/> TT Trinidad and Tobago |
| <input type="checkbox"/> IL Israel | <input type="checkbox"/> UA Ukraine |
| <input type="checkbox"/> IS Iceland | <input type="checkbox"/> UG Uganda |
| <input checked="" type="checkbox"/> JP Japan | <input checked="" type="checkbox"/> US United States of America |
| <input type="checkbox"/> KE Kenya | |
| <input type="checkbox"/> KG Kyrgyzstan | <input type="checkbox"/> UZ Uzbekistan |
| <input type="checkbox"/> KP Democratic People's Republic of Korea | <input type="checkbox"/> VN Viet Nam |
| | <input type="checkbox"/> YU Yugoslavia |
| <input type="checkbox"/> KR Republic of Korea | <input type="checkbox"/> ZW Zimbabwe |
| <input type="checkbox"/> KZ Kazakhstan | |
| <input type="checkbox"/> LC Saint Lucia | Check-boxes reserved for designating States (for the purposes of |
| <input type="checkbox"/> LK Sri Lanka | a national patent) which have become party to the PCT after |
| <input type="checkbox"/> LR Liberia | issuance of this sheet: |
| <input type="checkbox"/> LS Lesotho | <input type="checkbox"/> ID Indonesia |
| <input type="checkbox"/> LT Lithuania | |
| <input type="checkbox"/> LU Luxembourg | |

In addition to the designations made above, the applicant also makes under Rule 4.9(b) all designations which would be permitted under the PCT except the designation(s) of _____

The applicant declares that those additional designations are subject to confirmation and that any designation which is not confirmed before the expiration of 15 months from the priority date is to be regarded as withdrawn by the applicant at the expiration of that time limit. (Confirmation of a designation consists of the filing of a notice specifying that designation and the payment of the designation and confirmation fees. Confirmation must reach the receiving Office within the 15-month time limit.)

Box No. VI PRIORITY CLAIM

Further priority claims are indicated in the Supplemental Box ☐

The priority of the following earlier application(s) is hereby claimed:

Country (in which, or for which, the application was filed)	Filing Date (day, month, year)	Application No.	Office of filing (only for regional or international applications)
item (1) US	(04.10.96) 04 October 1996	60/026,761	
item (2) US	(18.04.97) 18 April 1997	60/044,736	
item (3)			

Mark the following check-box if the certified copy of the earlier application is to be issued by the Office which for the purposes of the present international application is the receiving Office (a fee may be required):

☒ The receiving Office is hereby requested to prepare and transmit to the International Bureau a certified copy of the earlier application(s) identified above as item(s): (1) and (2)

Box No. VII INTERNATIONAL SEARCHING AUTHORITY

Choice of International Searching Authority (ISA) (If two or more International Searching Authorities are competent to carry out the international search, indicate the Authority chosen; the two-letter code may be used):

ISA /US

Earlier search Fill in where a search (international, international-type or other) by the International Searching Authority has already been carried out or requested and the Authority is now requested to base the international search, to the extent possible, on the results of that earlier search. Identify such search or request either by reference to the relevant application (or the translation thereof) or by reference to the search request:

Country (or regional Office):

Date (day, month, year):

Number:

Box No. VIII CHECK LIST

This international application contains the following number of sheets:

1. request : 3 sheets
 2. description : 19 sheets
 3. claims : 4 sheets
 4. abstract : 1 sheets
 5. drawings : 14 sheets
 Total : 41 sheets


This international application is accompanied by the item(s) marked below:

1. ☒ separate signed power of attorney
 2. ☐ copy of general power of attorney
 3. ☐ statement explaining lack of signature
 4. ☐ priority document(s) identified in Box No. VI as item(s)
 5. ☒ fee calculation sheet
 6. ☐ separate indications concerning deposited microorganisms
 7. ☐ nucleotide and/or amino acid sequence listing (diskette)
 8. ☐ other (specify):

Figure No. 10 of the drawings (if any) should accompany the abstract when it is published.

Box No. IX SIGNATURE OF APPLICANT OR AGENT

Next to each signature, indicate the name of the person signing and the capacity in which the person signs (if such capacity is not obvious from reading the request).



Timothy E. Niednagel, Agent for Applicant

For receiving Office use only

1. Date of actual receipt of the purported international application:	2. Drawings: <input type="checkbox"/> received: <input type="checkbox"/> not received:
3. Corrected date of actual receipt due to later but timely received papers or drawings completing the purported international application:	
4. Date of timely receipt of the required corrections under PCT Article 11(2):	
5. International Searching Authority specified by the applicant: ISA /	6. <input type="checkbox"/> Transmittal of search copy delayed until search fee is paid

For International Bureau use only

Date of receipt of the record copy by the International Bureau:

PCT

POWER OF ATTORNEY

(for an international application filed under the Patent Cooperation Treaty)

(PCT Rule 90.4)

The undersigned applicant(s) (Names should be indicated as they appear in the request):

JONES, Charles W.
P.O. Box 161
Knightstown, Indiana 46148
US

hereby appoints (appoint) the following person as:

☒ agent

☐ common representative

Name and address

(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country.)

NIEDNAGEL, Timothy E.; COFFEY, William R.; HYLAND, Jerry E.; CONARD, Richard D.; LAMMERT, Steven R.; REZEK, Richard A.; PALAN, Perry; NEWMAN, Mark M.; GILLENWATER, Bobby B.; GZYBOWSKI, Michael S.; HUNT, Paul B.; BREEN, John P.; WERLING, Jill L.; HARRISON, Nancy J.; CARTER, R. Trevor; NULL, Robert D.; all located at:
BARNES & THORNBURG
11 South Meridian Street
Indianapolis, Indiana 46204
US

to represent the undersigned before

☒ all the competent International Authorities

☐ the International Searching Authority only

☐ the International Preliminary Examining Authority only

in connection with the international application identified below:

Title of the invention: STEREOGRAPHIC BOOK


Applicant's or agent's file reference: 6313-29114

International application number (if already available): PCT/US97/

filed with the following Office US
and to make or receive payments on behalf of the undersigned.

as receiving Office

Signature of the applicant(s) (where there are several applicants, each of them must sign: next to each signature, indicate the name of the person signing and the capacity in which the person signs, if such capacity is not obvious from reading the request or this power):


Charles W. JONES

Date:

(03.10.97)

03 October 1997

Day/ Month/ Year